

BHT MULLICA TOWNSHIP

SHEET 35, BLOCK 3503, LOTS 1 & 2; BLOCK 3504, LOTS 1 & 2; BLOCK 3505, LOT 1; BLOCK 3506, LOTS 1; BLOCK 3507, LOT 1; BLOCK 3508, LOT 1; BLOCK 3509, LOT 1 TOWNSHIP OF MULLICA, ATLANTIC COUNTY, NEW JERSEY

PRELIMINARY AND FINAL SITE PLANS






FEMA FLOOD INSURANCE RATE MAP

APPLICANT:

BHT PROPERTIES GROUP

5555 ANGLERS AVENUE, SUITE 27 FORT LAUDERAKE, FL 33312



MARATHON

Engineering & Environmental Services

3 Killdeer Court, Suite 302, Swedesboro, NJ 08085 1616 Pacific Avenue, Suite 501, Atlantic City, NJ 08401

EXISTING UTILITY INFORMATION SHOWN ON THESE PLANS IS FURNISHED BY THE UTILITY COMPANIES AND/OR THE SURVEYOR AND THE ACCURACY THEREOF IS NOT THE RESPONSIBILITY OF MARATHON ENGINEERING & ENVIRONMENTAL SERVICES, INC. IT IS THE RESPONSIBILITY OF THE OWNERS AND/OR CONTRACTOR TO CALL 1-800-272-1000 FOR FIELD LOCATION OF UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION.

APPLICANT'S INTENT

CERTIFICATION OF APPROVALS

7.11E OO/12E	ZONE <u>PT</u> AS NOTED	I HEREBY CERTIFY THAT THIS SITE PLAN APPROVED BY RESOLUTIONTOWNSHIP PLANNING BOARD.	
PPLICANT BHT PROPERTIES GR DDRESS 5555 ANGLERS AVENUE, SL	JITE 27	CHAIRPERSON	DATE
FORT LAUDERAKE, FL 3	33312	SECRETARY	DATE
HEREBY CERTIFY THAT I AM THE OWNER (HE PROPERTY HEREIN DEPICTED AND THAT //TH THIS PLAN. I CONSENT TO THE FILING	I CONCUR	BOARD ENGINEER	DATE
LAN WITH THE PLANNING BOARD OF MULLI		TOWNSHIP CLERK	DATE
WNER:	DATE	THIS SITE PLAN IS HEREBY APPROVED B COUNTY PLANNING BOARD.	Y THE ATLANTIC
WNER:	DATE	CHAIRPERSON	DATE
WNER:	DATE	SECRETARY	DATE

		SHEET INDEX
SHEET NO.	DWG. NO.	SHEET TITLE
1 OF 24	C0001	COVER SHEET
2 OF 24	C0002	INFORMATION SHEET
3 OF 24	C1801	EXISTING CONDITIONS PLAN
4 OF 24	D0101	DEMOLITION PLAN
5 OF 24	C0100	OVERALL SITE PLAN
6 OF 24	C0101	SITE PLAN - A
7 OF 24	C0102	SITE PLAN - B
8 OF 24	C0301	GRADING PLAN - A
9 OF 24	C0302	GRADING PLAN - B
10 OF 24	C0701	LIGHTING PLAN
11 OF 24	C1101	SITE DETAIL SHEET
12 OF 24	C1102	STORM SEWER DETAIL SHEET
13 OF 24	C1103	STORM SEWER DETAIL SHEET
14 OF 24	C1104	STORM SEWER DETAIL SHEET
15 OF 24	C1105	STORM SEWER DETAIL SHEET
15 OF 24	C1106	SOIL LOGS DETAIL SHEET
17 OF 24	C1107	SOIL LOGS DETAIL SHEET
18 OF 24	C1108	SOIL LOGS DETAIL SHEET
19 OF 24	C1201	SOIL EROSION AND SEDIMENT CONTROL PLAN - A
20 OF 24	C1202	SOIL EROSION AND SEDIMENT CONTROL PLAN - B
21 OF 24	C1203	SOIL COMPACTION PLAN - A
22 OF 24	C1204	SOIL COMPACTION PLAN - B
23 OF 24	C1301	SOIL EROSION AND SEDIMENT CONTROL NARRATIVE SHEET

24 OF 24 C1302 SOIL EROSION AND SEDIMENT CONTROL DETAIL SHEET

DRAFT | 1 | INITIAL SUBMISSION ISSUE DATE I ISSUE NO. I SUBMISSION / REVISION BHT MULLICA TOWNSHIP

. 35, BL 3503, LOTS 1 & 2, BL 3504, LOTS 1 & 2, BL 3505, LOT 1, BL 3506, LOT 1, BL 3507, LOTS 1 & 2, BL 3508, LOT 1, BL 3509, L0 TOWNSHIP OF MULLICA, ATLANTIC COUNTY, NEW JERSEY

COVER SHEET

BHT DESIGN GROUP



MARATHON

SK DJI

| BY | APPR

DAVID J. FLEMING, P.E.

U.S.G.S. EGG HARBOR CITY AND NEWTONVILLE QUAD MAP SCALE: 1" = 2,000'

PROJECT NOTES

A. GENERAL SITE NOTES

- THE TRACT FOR DEVELOPMENT CONSISTS OF SHEET 35, BLOCK 3503, LOTS 1 & 2, BLOCK 3504, LOTS 1 & 2, BLOCK 3505, LOT 1, BLOCK 3506, LOT 1, BLOCK 3507, LOTS 1 & 2, BLOCK 3508, LOT 1 AND BLOCK 3509, LOT 1, OF THE OFFICIAL TAX MAP OF MULLICA TOWNSHIP
- 2. THE TRACT FOR DEVELOPMENT IS ZONED PT (PINELANDS TOWN) TOTAL AREA OF TRACT = 44.18
- THE PROPOSED DEVELOPMENT SHALL BE SERVED BY A SEPTIC SYSTEM AND WELL 4. THE PROPOSED DEVELOPMENT SHALL COMPLY WITH THE CURRENT RECYCLING PROGRAM IN EFFECT IN
- MULLICA TOWNSHIP THE OWNER, OR HIS REPRESENTATIVE, SHALL DESIGNATE AN INDIVIDUAL RESPONSIBLE FOR CONSTRUCTION SITE SAFETY DURING THE COURSE OF SITE IMPROVEMENTS PURSUANT TO N.J.A.C.
- 6. GRADING AROUND BUILDINGS AND FINISHED FLOOR ELEVATIONS ARE SUBJECT TO CHANGE UPON REVIEW OF CONSTRUCTION PLANS OF PROPOSED BUILDINGS.

5:23-2.21 (E) OF THE N.J. UNIFORM CONSTRUCTION CODE AND CFR 1926.32 (F) (OSHA COMPETENT

- 7. ALL BARRIER FREE DESIGN AND CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST A.D.A. AND N.J.D.O.T. STANDARDS
- 8. ANY VARIATIONS FROM THE PLANS MUST BE AUTHORIZED BY THE DESIGN ENGINEER AND APPROVED BY
- THE TOWNSHIP ENGINEER. 9. CONSTRUCTION DETAILS/SHOP DRAWINGS UTILIZED BY THE CONTRACTOR SHALL BE REVIEWED AND APPROVED BY THE TOWNSHIP ENGINEER
- 10. REFER TO THE COMPLETE SET OF PLANS FOR ADDITIONAL INFORMATION. 11. THIS SET OF DRAWINGS AND ALL INFORMATION CONTAINED HEREIN IS AUTHORIZED FOR THE USE ONLY BY THE PARTY FOR WHOM THE WORK IS CONTRACTED OR WHOM IT IS CERTIFIED. THIS SET OF DRAWINGS MAY NOT BE COPIED, REUSED, DISCLOSED, DISTRIBUTED, OR RELIED UPON FOR ANY OTHER PURPOSE WITHOUT THE WRITTEN CONSENT OF MARATHON ENGINEERING & ENVIRONMENTAL SERVICES,
- 12. ANY DEMOLITION MATERIAL SHALL BE PROPERLY DISPOSED OF AND NO ON-SITE BURIAL IS PERMITTED. 13. ALL TRAFFIC SIGN PLACEMENT SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF MUTCD, U.S. DEPARTMENT OF TRANSPORTATION AS AMENDED. ALL SIGNS SHALL BE MOUNTED ON BREAKAWAY SIGN
- 14. THE APPLICANT SHALL NOTIFY THE MULLICA TOWNSHIP ENGINEER A MINIMUM OF 24 HOURS PRIOR TO THE START OF ANY CONSTRUCTION.

B. <u>SURVEY NOTES</u>

- ALL BEARINGS ARE SHOWN IN DEGREES, MINUTES AND SECONDS. HORIZONTAL DATUM IS IN FEET AND REFERENCES THE NEW JERSEY STATE PLANE COORDINATE SYSTEM (NAD 83 BASED ON GPS OBSERVATION) VERTICAL DATUM IS IN FEET AND REFERENCES NAVD '88.
- PLANIMETRIC FEATURES SHOWN HEREON PREPARED BY COOPER NOR EAST MAPPING AND COMPILED ON DIGITAL WORKSTATIONS USING AERIAL PHOTOGRAPHY TAKEN JULY 1, 2022. PLANIMETRIC FEATURES
- SHOWN HEREON HAVE BEEN VERIFIED BY FIELD SURVEY. 4. TOPOGRAPHY SHOWN HEREON CREATED FROM LIDAR POINT CLOUD. OBTAINED FROM NOAA OFFICE FOR COASTAL MANAGEMENT, 2019 U.S.G.S. LIDAR: CONED TOPOBATHYMETRIC MODEL FOR NEW JERSEY AND
- DELAWARE, NAVO 1988 U.S. FOOT. BOUNDARY INFORMATION WAS TAKEN FROM PLAN ENTITLED "ALTA/NSPS LAND TITLE SURVEY, WHITE HORSE PIKE (ROUTE 30), SHEET 35, BLOCK 3503, LOTS 1 & 2, BLOCK 3504, LOTS 1 & 2, BLOCK
- 3505, LOT 1, BLOCK 3506, LOT 1, BLOCK 3507, LOT 1, BLOCK 3508, LOT 1, BLOCK 3509, LOT 1, TOWNSHIP OF MULLICA, ATLANTIC COUNTY, NEW JERSEY", PREPARED BY MARATHON ENGINEERING & ENVIRONMENTAL SERVICES, INC., DATED xx/xx/2022, UNREVISED, PROJECT NO. BHT 001.03.

C. CONTRACTOR/OWNER RESPONSIBILITY NOTES

- THE CONTRACTOR/OWNER SHALL DESIGNATE A PERSON THAT IS KNOWLEDGEABLE OF CONSTRUCTION SAFETY STANDARDS AND IS EXPECTED TO BE AT THE CONSTRUCTION SITE ON A REGULAR BASIS. THIS PERSON SHALL BE RESPONSIBLE FOR THE IMPLEMENTATION, DISCHARGE, AND MONITORING OF SAFETY STANDARDS AND PRACTICES AT THE SITE. THE CONTRACTOR/OWNER SHALL PROVIDE DESIGN ENGINEER WITH NAME, ADDRESS AND TELEPHONE NUMBER OF THE DESIGNEE. IN LIEU OF THIS INFORMATION, THE REPRESENTATIVE PERSON FROM THE CONTRACTOR'S ORGANIZATION WHO SIGNED THE CONTRACT SHALL HEREBY BE RESPONSIBLE FOR THIS FUNCTION. 2. THE CONTRACTOR SHALL SCHEDULE ALL CONSTRUCTION TO BE IN ACCORDANCE WITH CURRENT O.S.H.A.
- THE SITE CONTRACTOR SHALL VERIFY WITH THE DESIGN ENGINEER WHAT PERMITS AND APPROVALS ARE PENDING OR HAVE BEEN APPROVED.
- THE SITE CONTRACTOR SHALL VERIFY AND MATCH HORIZONTAL AND VERTICAL ELEVATIONS. 5. THE CONTRACTOR SHALL PERFORM ALL WORK IN A WORKMANLIKE MANNER IN ACCORDANCE WITH ALL
- APPLICABLE CODES, ORDINANCES, AND MANUFACTURERS' RECOMMENDATIONS AND STANDARDS. 6. ALL DIMENSIONS AND EXISTING CONDITIONS MUST BE VERIFIED BY CONTRACTOR AND OWNER MUST BE
- NOTIFIED OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK. 7. ALL UNDERGROUND UTILITIES LOCATIONS ARE APPROXIMATE AND ARE TO BE VERIFIED IN THE FIELD BY
- THE CONTRACTOR AT THE TIME OF CONSTRUCTION. 8. THE CONTRACTOR SHALL VERIFY IN FIELD ALL CONDITIONS AS SHOWN ON THE PLANS AND SHALL BE
- RESPONSIBLE FOR FIELD MEASUREMENTS FOR ALL NEW CONSTRUCTION. REFER TO THE ARCHITECTURAL DRAWINGS FOR ANY INFORMATION NOT SHOWN HERE. 9. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SHORING, UNDERPINNING AND STRUCTURAL
- STABILITY DURING CONSTRUCTION. 10. THE CONTRACTOR SHALL CALL 1-800-272-1000 FOR FIELD LOCATIONS OF UNDERGROUND UTILITIES
- 11. IN THE EVENT CONDITIONS AT THE SITE ARE NOTICEABLY DIFFERENT (AT THE TIME OF CONSTRUCTION)
- FROM THE DOCUMENTS PROVIDED, THE CONTRACTOR AND/OR OWNER SHALL NOTIFY THE DESIGN
- ENGINEER IMMEDIATELY. 12. THE PROPOSED SITE GRADING DEPICTED IN THESE PLANS IS INTENDED TO PROVIDE A GENERAL GUIDE FOR GRADING. THE GENERAL CONTRACTOR, CONSTRUCTION MANAGER OR OWNER SHALL INSTRUCT THE
- CONCRETE CONTRACTOR TO TAKE CARE IN SETTING FORMS FOR PEDESTRIAN AREAS TO INSURE THAT THEY CONFORM TO THE NEW JERSEY BARRIER FREE SUBCODE. 13. THE CONTRACTOR SHALL COMPLY WITH ALL CONDITIONS OF APPROVAL IMPOSED BY ALL REGULATORY
- AGENCIES HAVING JURISDICTION AS IT RELATES TO THE CONSTRUCTION AND MAINTENANCE OF THE 14. CONTRACTOR DAMAGE TO ANY EXISTING FEATURE SUCH AS. BUT NOT LIMITED TO. CONCRETE CURBS. CONCRETE WALKS, PAVING, LIGHTS, PLANTERS, SIGNS, UTILITIES OR BUILDINGS NOT SCHEDULED FOR


REMOVAL SHALL BE RESTORED TO ORIGINAL CONDITION BY THE CONTRACTOR.

15. THE OWNER, OR HIS REPRESENTATIVE, IS TO DESIGNATE AN INDIVIDUAL RESPONSIBLE FOR CONSTRUCTION SITE SAFETY DURING THE COURSE OF SITE IMPROVEMENTS PURSUANT TO N.J.A.C. 5: 23-2.21 (E) OF THE N.J. UNIFORM CONSTRUCTION CODE AND CFR 1926.32 (F) (OSHA COMPETENT PERSON).

D. UTILITY NOTES

<u>GENERAL</u>

- a. ALL PROPOSED UTILITIES SHALL BE INSTALLED UNDERGROUND. b. ALL MATERIALS, METHODS AND DETAILS OF IMPROVEMENT CONSTRUCTION SHALL CONFORM TO THE REGULATIONS OF MULLICA TOWNSHIP, ATLANTIC COUNTY AND/OR THE APPROPRIATE UTILITY
- COMPANY, WHICHEVER REGULATION TAKES PRECEDENCE. c. WHERE IT IS NECESSARY TO CONNECT TO EXISTING UTILITIES WITHIN EXISTING ROADWAYS, THE CONTRACTOR SHALL PROVIDE ALL NECESSARY SAW CUTTING FOR WATER AND SEWER SERVICE.
- TRENCHING, BACKFILL, COMPACTION AND PAVING SHALL BE IN ACCORDANCE WITH MULLICA TOWNSHIP, ATLANTIC COUNTY AND NJDOT SPECIFICATIONS, AS APPLICABLE PIPE LENGTHS AND GRADIENTS ARE CALCULATED TO THE CENTERLINE OF SANITARY AND STORM SEWER STRUCTURES. ACTUAL PIPE LENGTH MAY BE LESS THAN CALCULATED LENGTH. AND SHOULD
- BE COMPUTED BY THE CONTRACTOR PRIOR TO CONSTRUCTION. e. EXISTING UTILITY INFORMATION SHOWN ON THIS PLAN IS FURNISHED BY THE UTILITY COMPANIES OR SURVEY PLAN BY THE SURVEYOR AND THE ACCURACY THEREOF IS NOT THE RESPONSIBILITY OF MARATHON ENGINEERING & ENVIRONMENTAL SERVICES, INC. IT IS THE RESPONSIBILITY OF THE OWNER AND/OR CONTRACTOR TO CALL 1-800-272-1000 FOR FIELD LOCATION OF UNDERGROUND



N.R.C.S. U.S. DEPARTMENT OF AGRICULTURE SOILS MAP SCALE: 1" = 1,000'

2. STORMWATER MANAGEMENT/STORM SEWERS

- STORMWATER MANAGEMENT SHALL BE IN ACCORDANCE WITH STANDARDS SET FORTH UNDER THE FOLLOWING DOCUMENTATION: THE NEW JERSEY STORMWATER BEST MANAGEMENT PRACTICES MANUAL
- NEW JERSEY ADMINISTRATIVE CODE 7:8. THE NEW JERSEY RESIDENTIAL SITE IMPROVEMENT STANDARDS, TITLE 5, CHAPTER 21 OF THE NEW JERSEY ADMINISTRATIVE CODE.
- MAINTENANCE OF ALL STORMWATER MANAGEMENT FACILITIES SHALL BE IN ACCORDANCE WITH THE STORMWATER MANAGEMENT FACILITIES MAINTENANCE MANUAL" PREPARED UNDER THE PROJECT. ALL HDPE PIPE SHALL CONFORM TO THE REQUIREMENTS OF AASHTO M252 AND M294. ALL REINFORCED CONCRETE PIPE SHALL CONFORM TO THE REQUIREMENTS OF ASTM C-76, CLASS III
- OR IV AS INDICATED. ALL CONCRETE STORM SEWER SHALL HAVE EITHER RUBBER GASKET OR BUTYL TAPE JOINTS AND BE WRAPPED WITH MORTAR AND FABRIC ON THE OUTSIDE. IN ADDITION, ALL 36 AND LARGER PIPE SHALL ALSO HAVE THE INSIDE OF THE JOINT MORTARED ALL DRAINAGE STRUCTURES. i.e., INLETS, MANHOLES AND ENDWALLS SHALL BE CONSTRUCTED IN ACCORDANCE WITH N.J.D.O.T. STANDARDS
- ALL INLETS SHALL HAVE BICYCLE SAFE ECO GRATES. BEDDING AND BACKFILL FOR THE REINFORCED CONCRETE PIPE AND HDPEP SHALL BE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.

3. GAS, ELECTRIC AND COMMUNICATIONS

- a. GAS. ELECTRIC AND COMMUNICATION SERVICE SHALL BE INSTALLED UNDERGROUND THROUGHOUT THE DEVELOPMENT IN ACCORDANCE WITH THE REGULATIONS OF THE LOCAL UTILITY COMPANIES AND
- b. ALL GAS SERVICE DESIGN AND CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE RULES AND REGULATIONS OF PSE & G.
- c. ALL ELECTRIC SERVICE DESIGN AND CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE RULES AND REGULATIONS OF PSE & G.
- d. ALL COMMUNICATIONS SERVICE DESIGN AND CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE RULES AND REGULATIONS OF VERIZON AND COMCAST.

E. PLACEMENT OF FILL MATERIAL

- 1. THE MATERIAL PLACED IN THE FILL SHALL BE FREE OF DETRIMENTAL AMOUNTS OF SOD, ROOTS, FROZEN SOIL, STONES MORE THAN SIX INCHES IN DIAMETER (EXCEPT ROCK FILLS), AND OTHER OBJECTIONABLE MATERIAL
- a. DRAIN FILL SHALL BE KEPT FROM BEING CONTAMINATED BY ADJACENT SOIL MATERIALS DURING PLACEMENT BY EITHER PLACING IT IN A CLEANLY EXCAVATED TRENCH, OR BY KEEPING THE DRAIN AT LEAST ONE FOOT ABOVE THE ADJACENT EARTH FILL. b. SELECTED DRAIN FILL AND BACKFILL MATERIAL SHALL BE PLACED AROUND STRUCTURES, PIPE
- CONDUITS, AND ANTI-SEEP COLLARS AT ABOUT THE SAME RATE ON ALL SIDES TO PREVENT DAMAGE FROM UNEQUAL LOADING. FILL MATERIAL SHALL BE PLACED AND SPREAD BEGINNING AT THE LOWEST POINT IN THE FOUNDATION, AND THEN BRINGING IT UP IN CONTINUOUS HORIZONTAL LAYERS THICK ENOUGH THAT THE REQUIRED COMPACTION CAN BE OBTAINED. THE FILL SHALL BE CONSTRUCTED IN CONTINUOUS LAYERS. IF OPENINGS OR SECTIONALIZED FILLS ARE REQUIRED, THE SLOPE OF THE BONDING SURFACES BETWEEN THE EMBANKMENT IN PLACE AND THE EMBANKMENT TO TO BE PLACED SHALL NOT BE STEEPER THAN THE RATIO OF THREE HORIZONTAL TO ONE VERTICAL. THE BONDING SURFACE SHALL BE TREATED THE SAME AS THAT SPECIFIED FOR THE FOUNDATION TO ENSURE A GOOD BOND WITH THE NEW FILL.
- THE DISTRIBUTION AND GRADATION OF MATERIALS SHALL BE SUCH THAT NO LENSES, POCKETS. STREAKS, OR LAYERS OF MATERIAL SHALL DIFFER SUBSTANTIALLY IN TEXTURE OF GRADATION FROM THE SURROUNDING MATERIAL. IF IT IS NECESSARY TO USE MATERIALS OF VARYING TEXTURE AND GRADATION, THE MORE IMPERVIOUS MATERIAL SHALL BE PLACED IN THE CENTER AND UPSTREAM PARTS OF THE FILL. IF ZONED FILLS OF SUBSTANTIALLY DIFFERING MATERIALS ARE SPECIFIED, THE ZONES SHALL BE PLACED ACCORDING TO LINES AND GRADES SHOWN ON THE DRAWINGS. THE COMPLETE WORK SHALL CONFORM TO THE LINES, GRADES, AND ELEVATIONS SHOWN IN THE DRAWINGS OR AS STAKED IN THE FIELD.
- d. THE MOISTURE CONTENT OF THE FILL MATERIAL SHALL BE ADEQUATE FOR OBTAINING THE REQUIRED COMPACTION. MATERIAL THAT IS TOO WET SHALL BE DRIED TO MEET THIS REQUIREMENT, AND MATERIAL THAT IS TOO DRY SHALL BE WETTED AND MIXED UNTIL THE REQUIREMENT IS MET. CONSTRUCTION EQUIPMENT SHALL BE OPERATED OVER EACH LAYER OF FILL TO ENSURE THAT THE REQUIRED COMPACTION IS OBTAINED. SPECIAL EQUIPMENT SHALL BE USED IF NEEDED TO OBTAIN THE REQUIRED COMPACTION. IF A MINIMUM REQUIRED DENSITY IS SPECIFIED, EACH LAYER OF FILL
- SHALL BE COMPACTED AS NECESSARY TO OBTAIN THAT DENSITY. e. FILL ADJACENT TO STRUCTURES, PIPE CONDUITS, AND DRAIN FILL OR ANTI-SEEP COLLARS SHALL BE COMPACTED TO A DENSITY EQUIVALENT TO THAT OF THE SURROUNDING FILL BY HAND TAMPING, OR BY USING MANUALLY DIRECTED POWER TAMPERS OR PLATE VIBRATORS. FILL ADJACENT TO CONCRETE STRUCTURES SHALL NOT BE COMPACTED UNTIL THE CONCRETE HAS HAD TIME TO GAIN ENOUGH STRENGTH TO SUPPORT THE LOAD.


SOILS DATA

AugaB AURA SAN	DY LOAM	2-5% SLOPE	"A" SOILS GROUP
EveB EVESBORO	SAND	0-5% SLOPE	"A" SOILS GROUP
FobB FORT MOT	T SAND	0-5% SLOPE	"A" SOILS GROUP
SOILS OBTAINED F AGRICULTURE.	ROM NATURAL RESOURCES CONSER\	/ATION SERVICES (NRCS) U.S. DEPARTMENT OF
ALL SOIL EROSION	AND SEDIMENT CONTROL IMPLEMEN	TATION SHALL BE IN AC	CORDANCE WITH

STANDARDS SET FORTH BY THE CAPE ATLANTIC CONSERVATION DISTRICT.

FLOOD DATA

- 1. A PORTION OF THE SITE IS LOCATED IN FLOOD ZONE "A" AS MAPPED ON THE FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAP FOR MULLICA TOWNSHIP, ATLANTIC COUNTY, NEW JERSEY, COMMUNITY PANEL NUMBER 34001C011OF, EFFECTIVE DATE AUGUST 28, 2018.
- 2. CERTAIN ACTIVITIES IN FLOOD HAZARD AREAS ARE REGULATED BY THE NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION AND SOME ACTIVITIES MAY BE PROHIBITED ON THIS SITE OR MAY FIRST REQURE A PERMIT.



OFFICIAL ZONING MAP OF MULLICA TOWNSHIP SCALE: 1" = 750'

ZONING SCHEDULE

THE DESIGN CRITERIA AND BULK/AREA REQUIREMENTS FOR THIS PROJECT ARE TAKEN FROM THE CODE OF THE TOWNSHIP OF MULLICA, LAND USE ORDINANCE ADOPTED 06/22/2021.

ZONE PT (PINELANDS TOWN)	PERMITTED OR REQUIRED	EXISTING CONDITIONS	PROPOSED IMPROVEMENTS	CONFORMITY STATUS
USE	VEHICLE SALES PER §144–123II	VACANT	USED VEHICLE SALES (§144–123II – SEE NOTES BELOW.)	CONFORMS
MINIMUM LOT AREA	1 ACRE	44.18 ACRES	44.18 ACRES	CONFORMS
MINIMUM LOT WIDTH	125 FT	2,850 FT	2,859 FT	CONFORMS
MINIMUM LOT FRONTAGE	100 FT	2,850 FT	2,850 FT	CONFORMS
MIN. IMPROVED LOT FRONTAGE	TOTAL LOT FRONTAGE	0 FT	TOTAL FRONTAGE	CONFORMS
MINIMUM FRONT YARD SETBACK	50 FT	N/A	185 FT	CONFORMS
MIN. FRONT YARD VEHICLE DISPLAY SETBACK	15 FT	N/A	80 FT	CONFORMS
MINIMUM SIDE YARD SETBACK	50 FT	N/A	80 FT	CONFORMS
MINIMUM REAR YARD SETBACK	50 FT	N/A	80 FT	CONFORMS
MAXIMUM BUILDING HEIGHT	1 STORY/20 FT	N/A	≤ 20 FT	CONFORMS
MAXIMUM BUILDING COVERAGE	25% OF TOTAL LAND AREA	N/A	0.45%	CONFORMS
	(PINELANDS TOWN) USE MINIMUM LOT AREA MINIMUM LOT WIDTH MINIMUM LOT FRONTAGE MIN. IMPROVED LOT FRONTAGE MINIMUM FRONT YARD SETBACK MIN. FRONT YARD VEHICLE DISPLAY SETBACK MINIMUM SIDE YARD SETBACK MINIMUM REAR YARD SETBACK MAXIMUM BUILDING HEIGHT	(PINELANDS TOWN) REQUIRED USE WEHICLE SALES PER \$144-123II MINIMUM LOT AREA 1 ACRE MINIMUM LOT WIDTH 125 FT MINIMUM LOT FRONTAGE 100 FT MIN. IMPROVED LOT FRONTAGE MINIMUM FRONT YARD SETBACK MIN. FRONT YARD VEHICLE DISPLAY SETBACK MINIMUM SIDE YARD SETBACK MINIMUM SIDE YARD SETBACK MINIMUM REAR YARD SETBACK MINIMUM REAR YARD SETBACK MAXIMUM BUILDING COVERAGE 25% OF TOTAL LAND	(PINELANDS TOWN) REQUIRED VEHICLE SALES PER \$144-123II MINIMUM LOT AREA 1 ACRE 44.18 ACRES MINIMUM LOT WIDTH 125 FT MINIMUM LOT FRONTAGE 100 FT 2,850 FT MINIMUM LOT FRONTAGE TOTAL LOT FRONTAGE 0 FT MINIMUM FRONT YARD SETBACK MIN. FRONT YARD VEHICLE DISPLAY SETBACK MINIMUM SIDE YARD SETBACK MINIMUM SIDE YARD SETBACK MINIMUM REAR YARD SETBACK 50 FT N/A MINIMUM REAR YARD SETBACK 50 FT N/A MAXIMUM BUILDING COVERAGE 25% OF TOTAL LAND N/A	(PINELANDS TOWN) REQUIRED CONDITIONS IMPROVEMENTS USE VEHICLE SALES PER §144-123II VACANT VEHICLE SALES PER §144-123II - SEE NOTES BELOW.) MINIMUM LOT AREA 1 ACRE 44.18 ACRES 44.18 ACRES 44.18 ACRES MINIMUM LOT WIDTH 125 FT 2,850 FT 2,850 FT MIN. IMPROVED LOT FRONTAGE 100 FT 2,850 FT TOTAL FRONTAGE MINIMUM FRONT YARD SETBACK 50 FT N/A 185 FT MIN. FRONT YARD VEHICLE DISPLAY SETBACK MINIMUM SIDE YARD SETBACK 50 FT N/A 80 FT MINIMUM REAR YARD SETBACK 50 FT N/A 80 FT MINIMUM REAR YARD SETBACK 50 FT N/A 80 FT MAXIMUM BUILDING COVERAGE 25% OF TOTAL LAND N/A 0.45%

<u>ORDINANCE §144–12311 (VEHICLE SALES (NEW OR USED VEHICLES)</u>

VEHICLE SALES (NEW OR USED VEHICLES). VEHICLE SALES ARE SUBJECT TO PLANNING BOARD APPROVAL AND SHALL BE PERMITTED IN THE EVC, NVC, DVC AND PT DISTRICTS, PROVIDED THAT:

- 1. SIZE OF SITE. THE SITE SHALL MEET THE MINIMUM LOT SIZE REQUIREMENTS FOR THE DISTRICT IN WHICH THE SITE IS LOCATED. 2. HEIGHT OF BUILDING. THE HEIGHT OF THE PRINCIPAL BUILDING SHALL NOT EXCEED ONE STORY, OR 20 FEET, IN THE OFFICE AND DISPLAY AREAS. A BUILDING USED FOR A SERVICE AREA SHALL NOT EXCEED THE HEIGHT OF 25 FEET.
- 3. BUILDING COVERAGE. ALL BUILDINGS COMBINED SHALL NOT COVER OR ENCOMPASS MORE THAN 25% OF TOTAL LAND AREA ALLOCATED TO SAID ESTABLISHMENTS.
- 4. SIGNS SHALL BE IN ACCORDANCE WITH THE SIGNS SECTION OF THIS CHAPTER.
- 5. SETBACKS. NO PART OF ANY BUILDING SHALL BE CLOSER THAN 50 FEET TO ANY PROPERTY LINE. NO VEHICLES SHALL BE DISPLAYED CLOSER THAN 15 FEET FROM THE FRONT YARD PROPERTY LINE.
- 6. PAVING AND DRAINAGE. ALL AREAS NOT REQUIRED FOR LANDSCAPING AND OTHER PURPOSES (WHETHER REGULATED BY THE ORDINANCE OR NOT) SHALL BE STONED AND PROPERLY DRAINED. 7. LANDSCAPING. ALL LANDSCAPING SHALL BE IN ACCORDANCE WITH THE LANDSCAPING REQUIREMENTS OF THIS CHAPTER.
- 8. ALL VEHICLE SERVICE ACTIVITIES AND OPERATIONS SHALL BE CONDUCTED WITHIN FULLY ENCLOSED STRUCTURES. NO COMMERCIAL GASOLINE STATIONS SHALL BE PERMITTED AS PART OF A VEHICLE SALES FACILITY. A GASOLINE DISPENSING FACILITY WHICH IS AN
- THE LOCATION OF THESE FACILITIES ON THE SITE. 9. ENTRANCES AND EXITS. ALL SERVICE ENTRANCES AND EXITS SHALL BE LOCATED AT THE REAR OR SIDE OF THE PRINCIPAL BUILDINGS. 10. LIGHTING. NO FLASHING OR FLICKERING LIGHTS MAY BE USED. EXTERIOR LIGHTING SHALL BE ARRANGED SO THAT IT IS DEFLECTED AWAY FROM ADJACENT LAND USES AND SHOULD BE ARRANGED SO AS NOT TO OBSTRUCT OR DETER THE VISIBILITY OF DRIVERS OR PEDESTRIANS. LIGHTING FIXTURES ILLUMINATING THE FRONT YARD AREA OF THE SITE SHALL NOT EXCEED 30 FEET IN HEIGHT AND SHALL

INTEGRAL PART OF SAID OPERATION AND IS NOT OPEN TO THE PUBLIC MAY BE PERMITTED, SUBJECT TO PLANNING BOARD APPROVAL OF

- BE ORNAMENTAL AND ARCHITECTURALLY COMPATIBLE WITH THE BUILDING. 11. ACCESS AND EGRESS FOR TRAFFIC. THERE SHALL BE ONE CURB CUT PERMITTED ALONG THE FRONT PROPERTY LINE OF THE SITE. ALL TRAFFIC ACCESS AND EGRESS POINTS SHALL BE SO DESIGNED TO ASSURE THE SAFE CIRCULATION OF VEHICULAR TRAFFIC TO AND FROM
- 12. FENCES AND WALLS. ANY FENCES OR WALLS MUST BE ERECTED SUBJECT TO THE CONDITIONS SET FORTH IN THIS CHAPTER. 13. ON-SITE PARKING. THERE SHALL BE ONE ON-SITE PARKING SPACE FOR EVERY FULL-TIME EMPLOYEE. IN ADDITION, THERE SHALL BE A MINIMUM OF FIVE CUSTOMER ON-SITE PARKING SPACES. EACH EMPLOYEE OR CUSTOMER ON-SITE PARKING SPACE SHALL BE CLEARLY
- 14. VEHICULAR TOWING SHALL BE PERMITTED AS AN ACCESSORY USE TO A VEHICLE SALES FACILITY. SCREENING OF VEHICLES ON THE SITE MUST COMPLY WITH THE DESIGN STANDARDS OF THIS CHAPTER.

PUBLIC UTILITIES

CONNECTIV REAL ESTATE DEPARTMENT 5100 HARDING HWY., SUITE 399 MAYS LANDING, NJ 08330-9902


PUBLIC SERVICE ELECTRIC & GAS COMPANY MANAGER-CORPORATE PROPERTIES 80 PARK PLAZA, T6B NEWARK, NJ 07102

STATE HIGHWAY ROUTE 30 1035 PARKWAY AVENUE TRENTON, NJ 08626



MARKED AND SHALL BE PROVIDED AS DEFINED IN THIS CHAPTER.

Call before you dig.



OFFICIAL TAX MAP OF MULLICA TOWNSHIP SCALE: 1" = 500'

MULLICA TOWNSHIP CERTIFIED OWNER'S LIST WITHIN 200'

BLK	LOT	CLASS	SOWNER NAME	STREET ADDRESS	CITY/STATE	ZIP	LOCATION
100	1	5A	STATE OF NEW JERSEY DOT	ONE PENN PLAZA E CN229	NEWARK, NJ	07105	RAILROAD 2,3,4,5,6,7,8,9,10
2707	1	4A	AW HOLDINGS, L.L.C.	3040 WHITE HORSE PIKE	HAMMONTON, NJ	08037	
2707	2	4A	PLAGEMAN, CONCETTA	3100 WHITE HORSE PIKE	HAMMONTON, NJ	08037	3100 WHITE HORSE PIKE
2707	4	1	McDERMOTT, JOHN & CHARMAYNE	2765 SEVENTH AVENUE	SWEETWATER, NJ	08037	3109 MOSS MILL ROAD
2718	1	1	CAPORALE, DANIEL P. (UCT)	3134 WHITE HORSE PIKE	HAMMONTON, NJ	08037	3122 WHITE HORSE PIKE
2728	1	4A	CAPORALE, DANIEL P. (UCT)	3134 WHITE HORSE PIKE	HAMMONTON, NJ	08037	3134-3136 WHITE HORSE PIKE
2738	1	1	CAPORALE, DANIEL P. (UCT)	3134 WHITE HORSE PIKE	HAMMONTON, NJ	08037	3142 WHITE HORSE PIKE
2801	1	1	JADA ENTERPRISES, L.L.C.	227 WHITE HORSE PIKE	HAMMONTON, NJ	08037. 1197	3200 WHITE HORSE PIKE
2811	1	1	JADA ENTERPRISES, L.L.C.	227 WHITE HORSE PIKE	HAMMONTON, NJ	08037. 1197	3208 WHITE HORSE PIKE
2821	1	1	JADA ENTERPRISES, L.L.C.	227 WHITE HORSE PIKE	HAMMONTON, NJ	08037. 1197	3218 WHITE HORSE PIKE
2821	2	4A	APONTE, MICHAEL A.	5018 MOSS MILL ROAD	EGG HARBOR CITY,	08215	3222 WHITE HORSE PIKE
2831	1	1	JADA ENTERPRISES, L.L.C.	227 WHITE HORSE PIKE	HAMMONTON, NJ	08037. 1197	3228 WHITE HORSE PIKE
2841	1	4A	COLUMBIA II PARTNERS	3238 WHITE HORSE PIKE	HAMMONTON, NJ	08037	3238 WHITE HORSE PIKE
2851	1	4A	NJ CARP APP TR & ED FUND	75 FIELDCREST AVENUE	EDISON, NJ	08837	3300 WHITE HORSE PIKE
3502	1	4A	EAST GATE MOBILE, L.L.C.	847 12th STREET	HAMMONTON, NJ	08037	3033 WHITE HORSE PIKE
3510	1	1	KML BUILDING CORP. NJ	650 RIDGE ROAD, STE #200	PITTSBURGH, PA	15205	3301 WHITE HORSE PIKE
3511	3	2	BEMBRY, EMMA GENE	3030 READING AVENUE	HAMMONTON, NJ	08037	3030 WHITE HORSE PIKE
3511	4	15F	MARTS, ROBERT V. & JENNIFER	3044 READING AVENUE	HAMMONTON, NJ	08037	3044 WHITE HORSE PIKE
3511	5	2	ADAMSON, JAMES & JEAN	P 0 BOX 348	ELWOOD, NJ	08217	3100 READING AVENUE
3511	6	2	ROBLIN, JAMES JR.	3106 READING AVENUE	HAMMONTON, NJ	08037	3106 READING AVENUE
3511	7	2	WILSBACH, JOSEPH A. & DONNA M.	3114 READING AVENUE	HAMMONTON, NJ	08037	3114 READING AVENUE
3511	8	2	BRACARELLO, RONNY LYNN	3128 READING AVENUE	HAMMONTON, NJ	08037	3128 READING AVENUE
3511	9	1	DE MARCO, ANTHONY C JR & MARY C	227 CHERRY STREET	HAMMONTON, NJ	08037	3132 READING AVENUE
3511	10	1	DI MATTEO, JOSEPH J. JR. & MARIE C.	3140 READING AVENUE	HAMMONTON, NJ	08037	3136 READING AVENUE
3511	11	2	DI MATTEO, JOSEPH J. JR. & MARIE C.	3140 READING AVENUE	HAMMONTON, NJ	08037	3140 READING AVENUE
3511	12	1	DI MATTEO, JOSEPH J. JR. & MARIE C.	3140 READING AVENUE	HAMMONTON, NJ	08037	3144 READING AVENUE
3511	13	1	DI MATTEO, JOSEPH J. JR. & MARIE C.	3140 READING AVENUE	HAMMONTON, NJ	08037	3148 READING AVENUE
3512	4	2	APPLEGATE, OLGA	2847 ALLENDALE PL. NW	WASHINGTON, DC	20008	3210 READING AVENUE
3512	5	2	IULIANETTI, JOHN L.	3212 READING AVENUE	HAMMONTON, NJ	08037	3212 READING AVENUE
3512	6.01	1	BROWN, DEANNA ALISE & K. DENELSBECK	745 SOUTH FIRST ROAD	HAMMONTON, NJ	08037	3226 READING AVENUE
3512	6.02	2	AMENDOLIA, DOMENIC P. III & MAGGIE M	3230 READING AVENUE	HAMMONTON, NJ	08037	3230 READING AVENUE
3512	7.01	2	PITTS, DAVID E. & LAURETTE J.	3252 READING AVENUE	HAMMONTON, NJ	08037	3252 READING AVENUE

DRAFT | 1 | INITIAL SUBMISSION ISSUE DATE | ISSUE NO. | SUBMISSION / REVISION BHT MULLICA TOWNSHIP T 35, BL 3503, LOTS 1 & 2, BL 3504, LOTS 1 & 2, BL 3505, LOT 1, BL 3506, LOT 1, BL 3507, LOTS 1 & 2, BL 3508, LOT 1, BL 3509, LOT

TOWNSHIP OF MULLICA, ATLANTIC COUNTY, NEW JERSEY

INFORMATION SHEET

BHT DESIGN GROUP 5555 ANGLERS AVENUE, SUITE 27 FORT LAUDERDALE, FL 33301

DAVID J. FLEMING, P.E.



| SK | DJF


BY APPR.

C0002

T DRAWN BY SHEET SK 2 OF 24


EXISTING UTILITY INFORMATION SHOWN ON THESE PLANS IS FURNISHED BY THE UTILITY COMPANIES AND/OR THE SURVEYOR AND THE ACCURACY THEREOF IS NOT THE RESPONSIBILITY OF MARATHON ENGINEERING & ENVIRONMENTAL SERVICES. INC. IT IS THE RESPONSIBILITY OF THE OWNERS AND/OR CONTRACTOR TO CALL 1-800-272-1000 FOR FIELD LOCATION OF UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION.


UTILITIES PRIOR TO CONSTRUCTION.




EXISTING UTILITY INFORMATION SHOWN ON THESE PLANS IS FURNISHED BY THE UTILITY COMPANIES AND/OR THE SURVEYOR AND THE ACCURACY THEREOF IS NOT THE RESPONSIBILITY OF MARATHON ENGINEERING & ENVIRONMENTAL SERVICES, INC. IT IS THE RESPONSIBILITY OF THE OWNERS AND/OR CONTRACTOR TO CALL 1-800-272-1000 FOR FIELD LOCATION OF UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION.

1 INCH = 80 FEET







ORDINANCE SECTION	ZONE PT (PINELANDS TOWN)	PERMITTED OR REQUIRED	EXISTING CONDITIONS	PROPOSED IMPROVEMENTS	CONFORMITY STATUS
§144–129.A.7	USE	VEHICLE SALES PER §144–123II	VACANT	USED VEHICLE SALES (§144–123II – SEE NOTES BELOW.)	CONFORMS
§144 Attachment 2	MINIMUM LOT AREA	1 ACRE	44.18 ACRES	44.18 ACRES	CONFORMS
§144 Attachment 2	MINIMUM LOT WIDTH	125 FT	2,850 FT	2,859 FT	CONFORMS
§144 Attachment 2	MINIMUM LOT FRONTAGE	100 FT	2,850 FT	2,850 FT	CONFORMS
§144 Attachment 2	MIN. IMPROVED LOT FRONTAGE	TOTAL LOT FRONTAGE	0 FT	TOTAL FRONTAGE	CONFORMS
§144–123.II.5	MINIMUM FRONT YARD SETBACK	50 FT	N/A	185 FT	CONFORMS
§144–123.II.5	MIN. FRONT YARD VEHICLE DISPLAY SETBACK	15 FT	N/A	80 FT	CONFORMS
§144-123.II.5	MINIMUM SIDE YARD SETBACK	50 FT	N/A	80 FT	CONFORMS
§144-123.II.5	MINIMUM REAR YARD SETBACK	50 FT	N/A	80 FT	CONFORMS
§144-123.II.2	MAXIMUM BUILDING HEIGHT	1 STORY/20 FT	N/A	≤ 20 FT	CONFORMS
§144–123.II.3	MAXIMUM BUILDING COVERAGE	25% OF TOTAL LAND AREA	N/A	0.45%	CONFORMS

ORDINANCE \$144-123II (VEHICLE SALES (NEW OR USED VEHICLES):

VEHICLE SALES (NEW OR USED VEHICLES). VEHICLE SALES ARE SUBJECT TO PLANNING BOARD APPROVAL AND SHALL BE PERMITTED IN THE EVC, NVC, DVC AND PT DISTRICTS, PROVIDED THAT:

- 1. SIZE OF SITE. THE SITE SHALL MEET THE MINIMUM LOT SIZE REQUIREMENTS FOR THE DISTRICT IN WHICH THE SITE IS LOCATED.
- 2. HEIGHT OF BUILDING. THE HEIGHT OF THE PRINCIPAL BUILDING SHALL NOT EXCEED ONE STORY, OR 20 FEET, IN THE OFFICE AND DISPLAY AREAS. A BUILDING USED FOR A SERVICE AREA SHALL NOT EXCEED THE HEIGHT OF 25 FEET.
- 3. BUILDING COVERAGE. ALL BUILDINGS COMBINED SHALL NOT COVER OR ENCOMPASS MORE THAN 25% OF TOTAL LAND AREA ALLOCATED TO SAID ESTABLISHMENTS.
- 4. SIGNS SHALL BE IN ACCORDANCE WITH THE SIGNS SECTION OF THIS CHAPTER.

BE ORNAMENTAL AND ARCHITECTURALLY COMPATIBLE WITH THE BUILDING.

- 5. SETBACKS, NO PART OF ANY BUILDING SHALL BE CLOSER THAN 50 FEET TO ANY PROPERTY LINE, NO VEHICLES SHALL BE DISPLAYED
- 6. PAVING AND DRAINAGE. ALL AREAS NOT REQUIRED FOR LANDSCAPING AND OTHER PURPOSES (WHETHER REGULATED BY THE ORDINANCE OR NOT) SHALL BE STONED AND PROPERLY DRAINED.
- 7. LANDSCAPING. ALL LANDSCAPING SHALL BE IN ACCORDANCE WITH THE LANDSCAPING REQUIREMENTS OF THIS CHAPTER.
- 8. ALL VEHICLE SERVICE ACTIVITIES AND OPERATIONS SHALL BE CONDUCTED WITHIN FULLY ENCLOSED STRUCTURES. NO COMMERCIAL GASOLINE STATIONS SHALL BE PERMITTED AS PART OF A VEHICLE SALES FACILITY. A GASOLINE DISPENSING FACILITY WHICH IS AN INTEGRAL PART OF SAID OPERATION AND IS NOT OPEN TO THE PUBLIC MAY BE PERMITTED, SUBJECT TO PLANNING BOARD APPROVAL OF THE LOCATION OF THESE FACILITIES ON THE SITE.
- 9. ENTRANCES AND EXITS. ALL SERVICE ENTRANCES AND EXITS SHALL BE LOCATED AT THE REAR OR SIDE OF THE PRINCIPAL BUILDINGS. 10. LIGHTING. NO FLASHING OR FLICKERING LIGHTS MAY BE USED. EXTERIOR LIGHTING SHALL BE ARRANGED SO THAT IT IS DEFLECTED AWAY FROM ADJACENT LAND USES AND SHOULD BE ARRANGED SO AS NOT TO OBSTRUCT OR DETER THE VISIBILITY OF DRIVERS OR PEDESTRIANS. LIGHTING FIXTURES ILLUMINATING THE FRONT YARD AREA OF THE SITE SHALL NOT EXCEED 30 FEET IN HEIGHT AND SHALL
- 11. ACCESS AND EGRESS FOR TRAFFIC. THERE SHALL BE ONE CURB CUT PERMITTED ALONG THE FRONT PROPERTY LINE OF THE SITE. ALL TRAFFIC ACCESS AND EGRESS POINTS SHALL BE SO DESIGNED TO ASSURE THE SAFE CIRCULATION OF VEHICULAR TRAFFIC TO AND FROM
- 12. FENCES AND WALLS. ANY FENCES OR WALLS MUST BE ERECTED SUBJECT TO THE CONDITIONS SET FORTH IN THIS CHAPTER. 13. ON-SITE PARKING. THERE SHALL BE ONE ON-SITE PARKING SPACE FOR EVERY FULL-TIME EMPLOYEE. IN ADDITION, THERE SHALL BE A MINIMUM OF FIVE CUSTOMER ON-SITE PARKING SPACE SHALL BE CLEARLY MARKED AND SHALL BE PROVIDED AS DEFINED IN THIS CHAPTER.
- 14. VEHICULAR TOWING SHALL BE PERMITTED AS AN ACCESSORY USE TO A VEHICLE SALES FACILITY. SCREENING OF VEHICLES ON THE SITE MUST COMPLY WITH THE DESIGN STANDARDS OF THIS CHAPTER.

SUBJECT BOUNDARY LIMIT RIGHT-OF-WAY LINE ADJACENT LOT LINE EASEMENT LINE EXISTING CHAIN LINK FENCE LINE EXISTING OVERHEAD WIRE LINE EXISTING WOODS LIMIT LINE EXISTING WATER BODY LINE PAVEMENT SURFACE AREA GRAVEL SURFACE AREA

PROPOSED WOODS LIMIT LINE

GRAPHIC SCALE

1 INCH = 80 FEET

ISSUE DATE ISSUE NO. BHT MULLICA TOWNSHIP SHT 35, BL 3503, LOTS 1 & 2, BL 3504, LOTS 1 & 2, BL 3505, LOT 1, BL 3506, LOT 1, BL 3507, LOTS 1 & 2, BL 3508, LOT 1, BL 3509, LOT TOWNSHIP OF MULLICA, ATLANTIC COUNTY, NEW JERSEY

OVERALL SITE PLAN BHT DESIGN GROUP

5555 ANGLERS AVENUE, SUITE 27

DRAFT 1 INITIAL SUBMISSION

Engineering & Environmental Services Swedesboro Office 3 Killdeer Court, Suite 302, Swedesboro, NJ 08085 ph (856) 241-9705 fax (856) 241-9709

SUBMISSION/REVISION


FORT LAUDERDALE, FL 33301 DAVID J. FLEMING, P.E.


Certificate of Authorization #24GA27995700 ALL DOCUMENTS PREPARED BY MARATHON ENGINEERING AND ENVIRONMENTAL SERVICES, INC. ARE INSTRUMENTS OF SERVICE IN RESPECT TO THE PROJECT. THEY ARE NOT INTENDED OR REPRESENTED TO BE SUITABLE FOR REUSE BY OWNER TO OTHERS ON EXTENSIONS OF THE PROJECT OR ON ANY OTHER PROJECT. ANY REUSE WITHOUT WRITTEN VERIFICATION OR ADAPTATION BY MARATHON ENGINEERING AND ENVIRONMENTAL SERVICES, INC. FOR THE SPECIFIC PURPOSE INTENDED WILL BE OWNERS SOLE RISK AND WITHOUT LIABILITY OR LEGAL EXPOSURE TO MARATHON ENGINEERING AND ENVIRONMENTAL SERVICES, INC. FROM SHALL INDEMNIFY AND HOLD HARMLESS MARATHON ENGINEERING AND ENVIRONMENTAL SERVICES, INC. FROM ALL CLAIMS, DAMAGES, LOSSES AND EXPENSES ARISING OUT OF OR RESULTING THEREFROM.


SK DJF


BY APPR.


EXISTING UTILITY INFORMATION SHOWN ON THESE PLANS IS FURNISHED BY THE UTILITY COMPANIES AND/OR THE SURVEYOR AND THE ACCURACY THEREOF IS NOT THE RESPONSIBILITY OF MARATHON ENGINEERING & ENVIRONMENTAL SERVICES, INC. IT IS THE RESPONSIBILITY OF THE OWNERS AND/OR CONTRACTOR TO CALL 1-800-272-1000 FOR FIELD LOCATION OF UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION.















LIGHT POLE TO BE CIMARRON CL1 LED LIGHT OR APPROVED EQUAL


WALL MOUNT & SINGLE/DOUBLE POLE LIGHT DETAIL


LUM	INAIRE	SCHE	DULE					
SYM.	LABEL	QTY	CATALOG NUMBER	DESCRIPTION	LAMP	IES FILE	LUMENS	LLF
•	À	3	CL1-A-90L-U-4K-4 SINGLE HEAD 25 FT POLE HEIGHT	CIMARRON CL1 SPAULDING LIGHTING	90 LEDS — TYPE IV COLOR 4,000 K	CL1-90L- 4K-4	22286	.95
	B	4	CL1-A-90L-U-4K-4 BACK-TO-BACK 25 FT POLE HEIGHT	CIMARRON CL1 SPAULDING LIGHTING	90 LEDS — TYPE IV COLOR 4,000 K	CL1-90L- 4K-4	22286	.95

LIGHTING NOTES


- 1. ALL LIGHTING SHALL BE IN ACCORDANCE WITH APPLICABLE STANDARDS.
- 2. NO SHADE TREE SHALL BE PLANTED CLOSER THAN 15 FEET TO ANY PROPOSED LIGHT STANCHION.
- 3. ALL LUMINARIES ARE UL LISTED & CSA CERTIFIED. 4. ALL LIGHTING FIXTURES AND POLES SHALL BE BEACON PRODUCTS OR APPROVED EQUAL.
- 5. ALONG CAR PARKING LOTS AND DRIVE AISLES UTILIZED BY CARS ONLY, THE LIGHTS SHALL BE SETBACK A MINIMUM OF 5 FEET FROM FACE OF CURB WHERE POSSIBLE.
- 6. LIGHTS SHALL BE PHOTO CONTROLLED.










LIGHT STANCHION DETAIL










ALL SUBGRADE SHALL HAVE 95% COMPACTION PER ASTM D 1557 OR APPROVED BY GEOTECHNICAL ENGINEER.

HEAVY-DUTY PAVING SECTION DETAIL N.T.S.



6" BOLLARD DETAIL

RECOMMENDED INTERSECTION SIGHT DISTANCES (ISD) FOR PASSENGER VEHICLES TURNING FROM STOP-CONTROLLED INTERSECTIONS ONTO THROUGH-TRAVEL STREETS ARE BASED ON THE NJDOT ROADWAY DESIGN MANUAL (REVISED 2008) FIGURE 6-A.


- d1 = DESIRABLE SIGHT DISTANCE ALONG THE HIGHWAY TO PERMIT A PASSENGER VEHICLE TO TURN LEFT.
- d2 = DESIRABLE SIGHT DISTANCE ALONG THE HIGHWAY TO PERMIT A PASSENGER VEHICLE TO TURN RIGHT OR CROSS.

FOR STOP-CONTROLLED INTERSECTION POSTED SPEED LIMIT = 50 MPH DESIGN SPEED LIMIT = 50 MPH


NJDOT (2008) RECOMMENDED ISD: d1 = 555 FT

d2 = 480 FTd1 OR d2 RIGHT TURN OR CROSSING LEFT TURN WHITE HORSE PIKE EDGE OF TRAVEL WAY -SIGHT TRIANGLE VERTEX ──**□□□□**__ SIGHT VERTEX OFFSET -ROW CENTERLINE LINE OF SIGHT (TYP)--STOP SIGN INSTALLED CENTERLINE OF STOP— CONTROLLED STREET OR— PER TRAFFIC MUTCD DRIVEWAY


SIGHT DISTANCE FOR STOP CONTROL INTERSECTIONS N.T.S.





DETECTABLE DOME WARNING SURFACE




BARRIER FREE PARKING DETAIL












TYPICAL STOP BAR DETAIL




COMBINATION SIDEWALK AND BELGIAN BLOCK CURB DETAIL N.T.S.







SEMI TRAILER TRUCK SIGHT DISTANCE DETAIL N.T.S.



DEPRESSED INTERIOR CURB DETAIL N.T.S.




DRAFT 1 INITIAL SUBMISSION SK DJF ISSUE DATE ISSUE NO. SUBMISSION/REVISION BY APPR. BHT MULLICA TOWNSHIP HT 35, BL 3503, LOTS 1 & 2, BL 3504, LOTS 1 & 2, BL 3505, LOT 1, BL 3506, LOT 1, BL 3507, LOTS 1 & 2, BL 3508, LOT 1, BL 3509, LOT TOWNSHIP OF MULLICA, ATLANTIC COUNTY, NEW JERSEY SITE DETAIL SHEET Engineering & Environmental Services Swedesboro Office BHT DESIGN GROUP 3 Killdeer Court, Suite 302, Swedesboro, NJ 08085 ph (856) 241-9705 fax (856) 241-9709 5555 ANGLERS AVENUE, SUITE 27 Certificate of Authorization #24GA27995700 FORT LAUDERDALE, FL 33301 DAVID J. FLEMING, P.E. JOCUMENTS PREPARED BY MARAITION ENGINEERING ENVIRONMENTAL SERVICES, INC. ARE INSTRUMENTS PROBLEM TO THE PROJECT. THEY ARE NOT DIED OR RESPECT TO THE PROJECT. THEY ARE NOT DIED OR REPRESENTED TO BE SUITABLE FOR REUSE WHER TO OTHERS ON EXTENSIONS OF THE PROJECT DRAWN BY SHEET SK 11 0F 24




SECTION A-A AGGREGATE SIZE #57) SECTION B-B


TYPE "A" NJDOT INLET DETAIL




TYPE "A" BICYCLE SAFE INLET GRATE DETAIL




TYPE "A" BICYCLE SAFE 'ECO' GRATE





MANHOLE STEP MANUFACTURED BY PARSON ENVIRONMENTAL PRODUCTS, INC. OR APPROVED EQUAL.

POLYPROPYLENE MANHOLE STEP DETAIL



NOTES:

- 1. <u>FOUNDATION</u>: WHERE THE TRENCH BOTTOM IS UNSTABLE, THE CONTRACTOR SHALL EXCAVATE TO A DEPTH REQUIRED BY THE ENGINEER AND REPLACE WITH A FOUNDATION OF CLASS I OR II MATERIAL AS DEFINED IN ASTM D2321, "STANDARD PRACTICE FOR INSTALLATION OF THERMOPLASTIC PIPE FOR SEWERS AND OTHER GRAVITY—FLOW APPLICATIONS," LATEST EDITION; AS AN ALTERNATIVE AND AT THE DISCRETION OF THE ENGINEER, THE TRENCH BOTTOM MAY BE STABILIZED USING A WOVEN GEOTEXTILE FABRIC.
- 2. <u>BEDDING</u>: SUITABLE MATERIAL SHALL BE AASHTO SIZE #57, CRUSHED, ANGULAR STONE INSTALLED AS REQUIRED IN ASTM D2321, LATEST EDITION. UNLESS OTHERWISE SPECIFIED BY THE ENGINEER, MINIMUM BEDDING THICKNESS SHALL BE 4" (100MM) FOR 4"-24" (100-600MM) AND 42"-48"(1050-1200MM) CORRUGATED POLYETHYLENE PIPE (CPEP); 6" (150MM) FOR 30"-36" (750-900MM) CPEP.


- 3. <u>HAUNCHING AND INITIAL BACKFILL</u>: SUITABLE MATERIAL SHALL BE AASHTO SIZE #57 CRUSHED, ANGULAR STONE INSTALLED AS REQUIRED IN ASTM D2321, LATEST EDITION.
- 4. UNLESS OTHERWISE SPECIFIED BY THE ENGINEER, MINIMUM TRENCH WIDTHS SHALL BE AS FOLLOWS:

NOMINAL Ø	MIN. RECOMMENDED
<u>in (mm)</u>	TRENCH WIDTH, in (mm)
4 (100)	21 (530)
6 (150)	23 (580)
8 (200)	25 (630)
10 (250)	28 (710)
12 (300)	31 (790)
15 (375)	34 (860)
18 (450)	39 (990)
24 (600)	48 (1220)
30 (750)	66 (1680)
36 (900)	78 (1980)
42 (1050)	83 (2110)
48 (1200)	89 (2260)
60 (1500)	102 (2590)

MINIMUM COVER: MINIMUM RECOMMENDED DEPTHS OF COVER FOR VARIOUS LIVE LOADING CONDITIONS ARE SUMMARIZED IN THE FOLLOWING TABLE. UNLESS OTHERWISE NOTED, ALL DIMENSIONS ARE TAKEN FROM THE TOP OF PIPE TO THE GROUND SURFACE.


SURFACE LIVE LOADING CONDITION	MINIMUM RECOMMENDED COVER, in (mm)
H25 (FLEXIBLE PAVEMENT) H25 (RIGID PAVEMENT)	12 (300)* 12 (300)
E80 RAILWAY HEAVY CONSTRUCTION	24 (610) 48 (1220)
*TOP OF PIPE TO BOTTOM	OF BITUMINOUS PAVEMENT SECTION

HDPE PIPE TRENCH/BEDDING DETAIL



NOTES:
ALL TRENCHING OPERATIONS SHALL CONFORM TO THE LATEST O.S.H.A.


STORM SEWER BEDDING FOR SUITABLE MATERIAL DETAIL N.T.S.




NOTES: ALL TRENCHING OPERATIONS SHALL CONFORM TO THE LATEST O.S.H.A. REQUIREMENTS.

STORM SEWER BEDDING FOR UNSUITABLE MATERIAL DETAIL N.T.S.


PIPE DIAMETER, IN (MM)						
11	10/12	15	18	24	30	36
DIAMETER (MM) (250/300)	(375)	(450)	(600)	(750)	(900)
11	N 42	41	49	59.5	88	88
A (MM	(1066)	(1041)	(1244)	(1511)	(2235)	(2235)
11	14.5	19	22	28	36	43
В (ММ	(368)	(482)	(558)	(711)	(914)	(1092)
11	33	34	43	48	63.5	66.5
C (MM	(838)	(863)	(1092)	(1219)	(1612)	(1689)
11	1 6	6	6	6	6	6
D (MM) (152)	(152)	(152)	(152)	(152)	(152)






BASIN OUTLET STRUCTURE DETAIL

N.T.S.






TRASH GRATE TO BE FACTORY MANUFACTURED AND ATTACHED ON SITE.


TRASH GRATE DETAIL

N.T.S.



THE MAXIMUM ROOF AREA THAT MAY BE CONNECTED TO EACH DOWNSPOUT SHALL BE LIMITED TO 600 SQUARE FEET.

ROOF DRAIN W/ SPLASH BLOCK DETAIL



09/16/2022

SK 12 OF 24





SC-740 STORMTECH CHAMBER SPECIFICATIONS

- CHAMBERS SHALL BE STORMTECH SC-740.
- 2. CHAMBERS SHALL BE ARCH-SHAPED AND SHALL BE MANUFACTURED FROM VIRGIN, IMPACT-MODIFIED POLYPROPYLENE COPOLYMERS.
- 3. CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2418-16a, "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- 4. CHAMBER ROWS SHALL PROVIDE CONTINUOUS, UNOBSTRUCTED INTERNAL SPACE WITH NO INTERNAL SUPPORTS THAT WOULD IMPEDE FLOW OR LIMIT ACCESS FOR INSPECTION.
- THE STRUCTURAL DESIGN OF THE CHAMBERS, THE STRUCTURAL BACKFILL, AND THE INSTALLATION REQUIREMENTS SHALL ENSURE THAT THE LOAD FACTORS SPECIFIED IN THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, SECTION 12.12, ARE MET FOR: 1) LONG-DURATION DEAD LOADS AND 2) SHORT-DURATION LIVE LOADS, BASED ON THE AASHTO DESIGN TRUCK WITH CONSIDERATION FOR IMPACT
- 6. CHAMBERS SHALL BE DESIGNED, TESTED AND ALLOWABLE LOAD CONFIGURATIONS DETERMINED IN ACCORDANCE WITH ASTM F2787, "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS". LOAD CONFIGURATIONS SHALL INCLUDE: 13 INSTANTANEOUS (<1 MIN) AASHTO DESIGN TRUCK LIVE LOAD ON MINIMUM COVER 2) MAXIMUM PERMANENT (75-YR) COVER LOAD AND 3) ALLOWABLE COVER WITH PARKED (1-WEEK) AASHTO DESIGN
- 7. REQUIREMENTS FOR HANDLING AND INSTALLATION:

OR YELLOW COLORS.

STORMTECH HIGHLY RECOMMENDS -FLEXSTORM INSERTS IN ANY UPSTREAM STRUCTURES WITH OPEN GRATES

ELEVATED BYPASS MANIFOLD -

SUMP DEPTH TBD BY

(24" [600 mm] MIN RECOMMENDED)

SITE DESIGN ENGINEER

- TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING, CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING STACKING LUGS.
- TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, a) THE ARCH STIFFNESS CONSTANT AS DEFINED IN SECTION 6.2.8 OF ASTM F2418 SHALL BE GREATER THAN OR EQUAL TO 550 LBS/IN/IN. AND b) TO RESIST CHAMBER DEFORMATION DURING INSTALLATION AT ELEVATED TEMPERATURES (ABOVE 73 $^{\circ}$ F / 23 $^{\circ}$ C), CHAMBERS SHALL BE PRODUCED FROM REFLECTIVE GOLD
- 8. ONLY CHAMBERS THAT ARE APPROVED BY THE SITE DESIGN ENGINEER WILL BE ALLOWED. UPON REQUEST BY THE SITE DESIGN ENGINEER OR OWNER. THE CHAMBER MANUFACTURER SHALL SUBMIT A STRUCTURAL EVALUATION FOR APPROVAL BEFORE DELIVERING CHAMBERS TO THE PROJECT SITE AS
- THE STRUCTURAL EVALUATION SHALL BE SEALED BY A REGISTERED PROFESSIONAL ENGINEER. THE STRUCTURAL EVALUATION SHALL DEMONSTRATE THAT THE SAFETY FACTORS ARE GREATER THAN OR EQUAL TO 1.95 FOR DEAD LOAD AND 1.75 FOR LIVE LOAD, THE MINIMUM REQUIRED BY ASTM F2787 AND BY SECTIONS 3 AND 12.12 OF THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS

DEAD LOAD DESIGN EXCEPT THAT IT SHALL BE THE 75-YEAR MODULUS USED FOR DESIGN.

THE TEST DERIVED CREEP MODULUS AS SPECIFIED IN ASTM F2418 SHALL BE USED FOR PERMANENT.

9. CHAMBERS AND END CAPS SHALL BE PRODUCED AT AN ISO 9001 CERTIFIED MANUFACTURING FACILITY.

COVER ENTIRE ISOLATOR ROW PLUS WITH ADS GEOSYNTHETICS 601T NON-WOVEN GEOTEXTILE

8' (2.4 m) MIN WIDE

OR MANHOLE

→ 12" (300 mm) MIN WIDTH

IMPORTANT - NOTES FOR THE BIDDING AND INSTALLATION OF THE SC-740

- 1. STORMTECH SC-740 CHAMBERS SHALL NOT BE INSTALLED UNTIL THE MANUFACTURER'S REPRESENTATIVE HAS COMPLETED A PRE-CONSTRUCTION MEETING WITH THE INSTALLERS.
- 2. STORMTECH SC-740 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
- 3. CHAMBERS ARE NOT TO BE BACKFILLED WITH A DOZER OR AN EXCAVATOR SITUATED OVER THE STORMTECH RECOMMENDS 3 BACKFILL METHODS:
- BACKFILL AS ROWS ARE BUILT USING AN EXCAVATOR ON THE FOUNDATION STONE OR SUBGRADE. BACKFILL FROM OUTSIDE THE EXCAVATION USING A LONG BOOM HOE OR EXCAVATOR.
- 4. THE FOUNDATION STONE SHALL BE LEVELED AND COMPACTED PRIOR TO PLACING CHAMBERS.
- 5. JOINTS BETWEEN CHAMBERS SHALL BE PROPERLY SEATED PRIOR TO PLACING STONE.

STONESHOOTER LOCATED OFF THE CHAMBER BED

- 6. MAINTAIN MINIMUM 6" (150 mm) SPACING BETWEEN THE CHAMBER ROWS. 7. EMBEDMENT STONE SURROUNDING CHAMBERS MUST BE A CLEAN, CRUSHED, ANGULAR STONE 3/4-2" (20-50 mm).
- 8. THE CONTRACTOR MUST REPORT ANY DISCREPANCIES WITH CHAMBER FOUNDATION MATERIALS BEARING CAPACITIES TO THE SITE DESIGN ENGINEER.
- 9. ADS RECOMMENDS THE USE OF "FLEXSTORM CATCH IT" INSERTS DURING CONSTRUCTION FOR ALL INLETS TO PROTECT THE SUBSURFACE STORMWATER MANAGEMENT SYSTEM FROM CONSTRUCTION SITE

NOTES FOR CONSTRUCTION EQUIPMENT

- 1. STORMTECH SC-740 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
- 2. THE USE OF CONSTRUCTION EQUIPMENT OVER SC-740 CHAMBERS IS LIMITED: NO EQUIPMENT IS ALLOWED ON BARE CHAMBERS.
- NO RUBBER TIRED LOADERS, DUMP TRUCKS, OR EXCAVATORS ARE ALLOWED UNTIL PROPER FILL DEPTHS ARE REACHED IN ACCORDANCE WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
- WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT CAN BE FOUND IN THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".

3. FULL 36" (900 mm) OF STABILIZED COVER MATERIALS OVER THE CHAMBERS IS REQUIRED FOR DUMP TRUCK TRAVEL OR DUMPING. USE OF A DOZER TO PUSH EMBEDMENT STONE BETWEEN THE ROWS OF CHAMBERS MAY CAUSE DAMAGE TO

THE CHAMBERS AND IS NOT AN ACCEPTABLE BACKFILL METHOD. ANY CHAMBERS DAMAGED BY THE "DUMP AND PUSH" METHOD ARE NOT COVERED UNDER THE STORMTECH STANDARD WARRANTY. CONTACT STORMTECH AT 1-888-892-2694 WITH ANY QUESTIONS ON INSTALLATION REQUIREMENTS OR WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT.


OPTIONAL INSPECTION PORT


SC-740 END CAP

ONE LAYER OF ADSPLUS125 WOVEN GEOTEXTILE BETWEEN

5' (1.5 m) MIN WIDE CONTINUOUS FABRIC WITHOUT SEAMS

FOUNDATION STONE AND CHAMBERS





 \propto

SHEET


INSERTA-TEE SIDE INLET DETAIL SC-740 TECHNICAL SPECIFICATIONS

	MATERIAL LOCATION	DESCRIPTION	AASHTO MATERIAL CLASSIFICATIONS	COMPACTION / DENSITY REQUIREMENT
D	FINAL FILL: FILL MATERIAL FOR LAYER 'D' STARTS FROM THE TOP OF THE 'C' LAYER TO THE BOTTOM OF FLEXIBLE PAVEMENT OR UNPAVED FINISHED GRADE ABOVE. NOTE THAT PAVEMENT SUBBASE MAY BE PART OF THE 'D' LAYER.	ANY SOIL/ROCK MATERIALS, NATIVE SOILS, OR PER ENGINEER'S PLANS. CHECK PLANS FOR PAVEMENT SUBGRADE REQUIREMENTS.	N/A	PREPARE PER SITE DESIGN ENGINEER'S PLANS. PAVED INSTALLATIONS MAY HAVE STRINGENT MATERIAL AND PREPARATION REQUIREMENTS.
С	INITIAL FILL: FILL MATERIAL FOR LAYER 'C' STARTS FROM THE TOP OF THE EMBEDMENT STONE ('B' LAYER) TO 18" (450 mm) ABOVE THE TOP OF THE CHAMBER. NOTE THAT PAVEMENT SUBBASE MAY BE A PART OF THE 'C' LAYER.	GRANULAR WELL-GRADED SOIL/AGGREGATE MIXTURES, <35% FINES OR PROCESSED AGGREGATE. MOST PAVEMENT SUBBASE MATERIALS CAN BE USED IN LIEU OF THIS LAYER.	AASHTO M145 ¹ A-1, A-2-4, A-3 OR AASHTO M43 ¹ 3, 357, 4, 467, 5, 56, 57, 6, 67, 68, 7, 78, 8, 89, 9, 10	BEGIN COMPACTIONS AFTER 12" (300 mm) OF MATERIAL OV THE CHAMBERS IS REACHED. COMPACT ADDITIONAL LAYER: 6" (150 mm) MAX LIFTS TO A MIN. 95% PROCTOR DENSITY FO WELL GRADED MATERIAL AND 95% RELATIVE DENSITY FO PROCESSED AGGREGATE MATERIALS. ROLLER GROSS VEHICLE WEIGHT NOT TO EXCEED 12,000 lbs (53 kN). DYNAM FORCE NOT TO EXCEED 20,000 lbs (89 kN).
В	EMBEDMENT STONE: FILL SURROUNDING THE CHAMBERS FROM THE FOUNDATION STONE ('A' LAYER) TO THE 'C' LAYER ABOVE.	CLEAN, CRUSHED, ANGULAR STONE	AASHTO M43 ¹ 3, 357, 4, 467, 5, 56, 57	NO COMPACTION REQUIRED.
А	FOUNDATION STONE: FILL BELOW CHAMBERS FROM THE SUBGRADE UP TO THE FOOT (BOTTOM) OF THE CHAMBER.	CLEAN, CRUSHED, ANGULAR STONE	AASHTO M43¹ 3, 357, 4, 467, 5, 56, 57	PLATE COMPACT OR ROLL TO ACHIEVE A FLAT SURFACE.

ACCEPTABLE FILL MATERIALS: STORMTECH SC-740 CHAMBER SYSTEMS

PLEASE NOTE . THE LISTED AASHTO DESIGNATIONS ARE FOR GRADATIONS ONLY. THE STONE MUST ALSO BE CLEAN, CRUSHED, ANGULAR. FOR EXAMPLE, A SPECIFICATION FOR #4 STONE WOULD STATE: "CLEAN, CRUSHED, ANGULAR NO. 4 (AASHTO M43) STONE".


STORMTECH COMPACTION REQUIREMENTS ARE MET FOR 'A' LOCATION MATERIALS WHEN PLACED AND COMPACTED IN 6" (150 mm) (MAX) LIFTS USING TWO FULL COVERAGES WITH A VIBRATORY COMPACTOR. WHERE INFILTRATION SURFACES MAY BE COMPROMISED BY COMPACTION, FOR STANDARD DESIGNS, CONTACT STORMTECH FOR COMPACTION REQUIREMENTS. 4. ONCE LAYER 'C' IS PLACED, ANY SOIL/MATERIAL CAN BE PLACED IN LAYER 'D' UP TO THE FINISHED GRADE. MOST PAVEMENT SUBBASE SOILS CAN BE USED TO REPLACE THE MATERIAL REQUIREMENTS OF LAYER 'C' OR 'D' AT THE SITE DESIGN ENGINEER'S DISCRETION.



- 1. CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2418-16a, "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS". 2. SC-740 CHAMBERS SHALL BE DESIGNED IN ACCORDANCE WITH ASTM F2787 "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- 3. THE SITE DESIGN ENGINEER IS RESPONSIBLE FOR ASSESSING THE BEARING RESISTANCE (ALLOWABLE BEARING CAPACITY) OF THE SUBGRADE SOILS AND THE DEPTH OF FOUNDATION STONE WITH CONSIDERATION FOR THE RANGE OF EXPECTED SOIL MOISTURE CONDITIONS.
- 4. PERIMETER STONE MUST BE EXTENDED HORIZONTALLY TO THE EXCAVATION WALL FOR BOTH VERTICAL AND SLOPED EXCAVATION WALLS.
- 5. REQUIREMENTS FOR HANDLING AND INSTALLATION: TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING, CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING STACKING LUGS. TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER JOINT SHALL NOT BE LESS THAN 2".
- TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, a) THE ARCH STIFFNESS CONSTANT AS DEFINED IN SECTION 6.2.8 OF ASTM F2418 SHALL BE GREATER THAN OR EQUAL TO 550 LBS/IN/IN. AND b) TO RESIST CHAMBER DEFORMATION DURING INSTALLATION AT ELEVATED TEMPERATURES (ABOVE 73° F / 23° C), CHAMBERS SHALL BE PRODUCED FROM REFLECTIVE GOLD OR YELLOW

SC-740 CROSS SECTION DETAIL

CONCRETE COLLAR NOT REQUIRED FOR UNPAVED APPLICATIONS **INSPECTION & MAINTENANCE** CONCRETE COLLAR NYLOPLAST INSPECTION POR PAVEMENT BODY (PART# 2708AG4IPKIT) OR FRAFFIC RATED BOX W/SOLID LOCKING COVER



INSPECTION PORTS MAY BE CONNECTED THROUGH ANY CHAMBER CORRUGATION CREST.

4" PVC INSPECTION PORT DETAIL (SC SERIES CHAMBER)

- STEP 1) INSPECT ISOLATOR ROW PLUS FOR SEDIMENT A INSPECTION PORTS (IF PRESENT)
 - REMOVE/OPEN LID ON NYLOPLAST INLINE DRAIN REMOVE AND CLEAN FLEXSTORM FILTER IF INSTALLED
 - USING A FLASHLIGHT AND STADIA ROD, MEASURE DEPTH OF SEDIMENT AND RECORD ON MAINTENANCE LOG LOWER A CAMERA INTO ISOLATOR ROW PLUS FOR VISUAL INSPECTION OF SEDIMENT LEVELS (OPTIONAL) IF SEDIMENT IS AT, OR ABOVE, 3" (80 mm) PROCEED TO STEP 2. IF NOT, PROCEED TO STEP 3. B. ALL ISOLATOR PLUS ROWS REMOVE COVER FROM STRUCTURE AT UPSTREAM END OF ISOLATOR ROW PLUS
- USING A FLASHLIGHT, INSPECT DOWN THE ISOLATOR ROWPLUS THROUGH OUTLET PIPE MIRRORS ON POLES OR CAMERAS MAY BE USED TO AVOID A CONFINED SPACE ENTRY) FOLLOW OSHA REGULATIONS FOR CONFINED SPACE ENTRY IF ENTERING MANHOLE B.3. IF SEDIMENT IS AT, OR ABOVE, 3" (80 mm) PROCEED TO STEP 2. IF NOT, PROCEED TO STEP 3.
- STEP 2) CLEAN OUT ISOLATOR ROW PLUS USING THE JETVAC PROCESS A. A FIXED CULVERT CLEANING NOZZLE WITH REAR FACING SPREAD OF 45" (1.1 m) OR MORE IS PREFERRED B. APPLY MULTIPLE PASSES OF JETVAC UNTIL BACKFLUSH WATER IS CLEAN C. VACUUM STRUCTURE SUMP AS REQUIRED
- STEP 3) REPLACE ALL COVERS, GRATES, FILTERS, AND LIDS; RECORD OBSERVATIONS AND ACTIONS. STEP 4) INSPECT AND CLEAN BASINS AND MANHOLES UPSTREAM OF THE STORMTECH SYSTEM.

SC-740 CHAMBER

SC-740 ISOLATOR ROW PLUS DETAIL

24" (600 mm) HDPE ACCESS PIPE REQUIRED

WITH FLAMP PART #: SC740EPE24BR

USE FACTORY PRE-FABRICATED END CAP


1. INSPECT EVERY 6 MONTHS DURING THE FIRST YEAR OF OPERATION. ADJUST THE INSPECTION INTERVAL BASED ON PREVIOUS OBSERVATIONS OF SEDIMENT ACCUMULATION AND HIGH WATER ELEVATIONS. 2. CONDUCT JETTING AND VACTORING ANNUALLY OR WHEN INSPECTION SHOWS THAT MAINTENANCE IS NECESSARY.

DRAFT 1 INITIAL SUBMISSION | SK | DJF ISSUE DATE ISSUE NO. SUBMISSION / REVISION BY APPR. BHT MULLICA TOWNSHIP T 35, BL 3503, LOTS 1 & 2, BL 3504, LOTS 1 & 2, BL 3505, LOT 1, BL 3506, LOT 1, BL 3507, LOTS 1 & 2, BL 3508, LOT 1, BL 3509, LOT TOWNSHIP OF MULLICA, ATLANTIC COUNTY, NEW JERSEY MARATHON STORM SEWER DETAIL SHEET Engineering & Environmental Services Swedesboro Office BHT DESIGN GROUP 3 Killdeer Court, Suite 302, Swedesboro, NJ 08085 ph (856) 241-9705 fax (856) 241-9709 5555 ANGLERS AVENUE, SUITE 27 Certificate of Authorization #24GA27995700 FORT LAUDERDALE, FL 33301 CUMENTS PREPARED BY MARATHON ENGINEERING SCALE DAVID J. FLEMING, P.E. ENVIRONMENTAL SERVICES, INC. ARE INSTRUMENTS
RVICE IN RESPECT TO THE PROJECT. THEY ARE NOT
DED OR REPRESENTED TO BE SUITABLE FOR REUSE

AS SHOWN DRAWN BY SHEET SK 13 0F 24

09/16/2022

EXISTING UTILITY INFORMATION SHOWN ON THESE PLANS IS FURNISHED BY THE UTILITY COMPANIES AND/OR THE SURVEYOR AND THE ACCURACY THEREOF IS NOT THE RESPONSIBILITY OF MARATHON ENGINEERING & ENVIRONMENTAL SERVICES, INC. IT IS THE RESPONSIBILITY OF THE OWNERS AND/OR CONTRACTOR TO CALL 1-800-272-1000 FOR FIELD LOCATION OF UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION.



BASIN NOTES:

WITH LIGHT WEIGHT, RUBBER TIRED EQUIPMENT.


- 1. PRIOR TO THE BASINS CONSTRUCTION THE AREA RESERVED FOR BASIN CONSTRUCTION SHALL BE CORDONED OFF TO PREVENT CONSTRUCTION EQUIPMENT AND STOCKPILED MATERIALS FROM COMPACTING THE SUBGRADE
- 2. DURING THE BASIN CONSTRUCTION, PRECAUTIONS SHOULD BE TAKEN TO PREVENT BOTH SUBGRADE SOIL
- COMPACTION AND SEDIMENT CONTAMINATION. ALL EXCAVATION SHOULD BE PERFORMED WITH THE LIGHTEST PRACTICAL EXCAVATION EQUIPMENT.
- 4. ALL EXCAVATION EQUIPMENT SHOULD BE PLACED OUTSIDE THE LIMITS OF THE BASIN. 5. TO PREVENT SUBGRADE SOIL CONTAMINATION AND CLOGGING BY SEDIMENT, FINAL BASIN CONSTRUCTION STABILIZATION SHOULD BE DELAYED UNTIL ALL OTHER CONSTRUCTION WITHIN THE DRAINAGE AREA IS COMPLETED AND THE DRAINAGE AREA STABILIZED. IF THE BASIN CONSTRUCTION CANNOT BE DELAYED UNTIL


ITS DRAINAGE AREA IS STABILIZED, DIVERSION BERMS, SILT FENCES, OR OTHER SUITABLE MEASURES SHOULD

BE PLACED AROUND THE BASIN PERMITER DURING ALL PHASES OF CONSTRUCTION TO PREVENT SEDIMENT FROM ENTERING THE BASIN. 6. ONCE THE FINAL GRADING PHASE OF AN INFILTRATION BASIN IS REACHED THE BOTTOM OF THE BASIN SHOULD BE DEEPLY TILLED WITH A ROTARY TILLER OR DISC HARROW AND THEN SMOOTHED OUT WITH A LEVELING DRAG OR EQUIVALENT GRADING EQUIPMENT. PROCEDURES SHOULD BE PERFORMED WITH EQUIPMENT LOCATED OUTSIDE THE BASIN BOTTOM. IF THIS IS NOT POSSIBLE, IT SHOULD BE PERFORMED


TYPICAL BASIN SECTION DETAIL


NJ PINELANDS STORMWATER BMP-SOIL PROFILE CROSS-SECTION






NJ PINELANDS STORMWATER BMP-SOIL PROFILE CROSS-SECTION







SPILLWAY DETAIL

NJ PINELANDS STORMWATER BMP-SOIL PROFILE CROSS-SECTION







NJ PINELANDS STORMWATER BMP-SOIL PROFILE CROSS-SECTION



NJ PINELANDS STORMWATER BMP-SOIL PROFILE CROSS-SECTION



NJ PINELANDS STORMWATER BMP-SOIL PROFILE CROSS-SECTION



NJ PINELANDS STORMWATER BMP-SOIL PROFILE CROSS-SECTION

xx.xx (SHWT)

SOIL REPLACEMENT

IS NOT PROPOSED

HIGHEST SHWT ELEVATION = xx.xx

) THE BASIN BOTTOM ELEVATION IS xx.xx

3) LOWEST ELEVATION (INVERT) OF BMP BOTTOM = xx.xx

5) SOIL REPLACEMENT IS NOT PROPOSED

a. SHWT (2.15').

TO ELEV. N/A

IN/HR & 2.07 IN/HR).

) DISTANCE BETWEEN BOTTOM OF BMP AND

S) IF PROPOSED, SOIL REPLACEMENT EXTENDS

) ELEV. AND RATES OF THE PERM. TESTS:

TP-6 (16-22" BELOW GRADE, 5.53

SEE SOIL LOGS FOR THE SOIL DESCRIPTION.

Structure Name <u>BASIN</u>

EL.xx.xx

EL. xx.xx

Test Pit X

10YR 3/2 SAND

10YR 5/6 SAND

10YR 4/6 LOAMY SAND

10YR 6/3 COARSE SAND, 7.5YR 4/6 MOTTLES; SINGLE GRAIN, SATURATION STARTING AT 58"

0" ORIG GRADE 93.77

__

92

91

90

89


86

85 +102" TEST PIT COMPLETED @119.6


—— 51**"**⊢


93 6" 10Y

Test Pit X 0" ORIG GRADE 93.77 10YR 3/2 SAND SPILLWAY ELEV.= xx.xx <u>93</u> 10YR 5/6 SAND ___




NJ PINELANDS STORMWATER BMP-SOIL PROFILE CROSS-SECTION







FOR FIELD LOCATION OF UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION.




I) HIGHEST SHWT ELEVATION = xx.xx Structure Name <u>BASIN X</u> Test Pit X 0" ORIG GRADE 93.77 2) THE BASIN BOTTOM ELEVATION IS xx.xx 10YR 3/2 SAND SPILLWAY ELEV.= xx.xx ___ 3) LOWEST ELEVATION (INVERT) OF BMP BOTTOM = xx.xx 93 6" 93.27 10YR 5/6 SAND 4) DISTANCE BETWEEN BOTTOM OF BMP AND a. SHWT (2.15'). 15* 92.55 10YR 4/6 LOAMY SAND 5) SOIL REPLACEMENT IS NOT PROPOSED 92 6) IF PROPOSED, SOIL REPLACEMENT EXTENDS TO ELEV. N/A ● ELEV. xx.xx ___) ELEV. AND RATES OF THE PERM. TESTS: TP-6 (16-22" BELOW GRADE, 5.53 IN/HR & 2.07 IN/HR). xx.xx (SHWT) 10YR 6/3 LOAMY SAND ___ SEE SOIL LOGS FOR THE SOIL DESCRIPTION. 90 ___ **——** 51**"** 89 10YR 6/3 COARSE SAND, 7.5YR 4/6 MOTTLES; SINGLE GRAIN, SATURATION STARTING AT 58* SOIL REPLACEMENT IS NOT PROPOSED <u>87</u>


NJ PINELANDS STORMWATER BMP-SOIL PROFILE CROSS-SECTION



















NJ PINELANDS STORMWATER BMP-SOIL PROFILE CROSS-SECTION






SOIL REPLACEMENT IS NOT PROPOSED

10YR 6/3 COARSE SAND, 7.5YR 4/6 MOTTLES; SINGLE GRAIN, SATURATION STARTING AT 58"


88

87


86










NJ PINELANDS STORMWATER BMP-SOIL PROFILE CROSS-SECTION




NJ PINELANDS STORMWATER BMP-SOIL PROFILE CROSS-SECTION








NJ PINELANDS STORMWATER BMP-SOIL PROFILE CROSS-SECTION





EXISTING UTILITY INFORMATION SHOWN ON THESE PLANS IS FURNISHED BY THE UTILITY COMPANIES AND/OR THE SURVEYOR AND THE ACCURACY THEREOF IS NOT THE RESPONSIBILITY OF MARATHON ENGINEERING & ENVIRONMENTAL SERVICES, INC. IT IS THE RESPONSIBILITY OF THE OWNERS AND/OR CONTRACTOR TO CALL 1-800-272-1000 FOR FIELD LOCATION OF UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION.

09/16/2022

SK 15 0F 24

DRAFT 1 INITIAL SUBMISSION
ISSUE DATE ISSUE NO. SUBMISSION/REVISION

BHT MULLICA TOWNSHIP

SIT 35, R. 3903, LOTS 1 & 2, R. 3904, LOTS 1 & 2, R. 3905, LOT 1, R. 3905, LOT 1

TOWNSHIP OF MULLICA, ATLANTIC COUNTY, NEW JERSEY

MARATHON

Engineering & Environmental Services

Swedesboro Office

3 Killdeer Court, Suite 302, Swedesboro, NJ 08085
ph (866) 241-9705 fax (866) 241-9705 fax (866) 241-9705

Certificate of Authorization #24GA27995700

DAVID J. FLEMING, P.E.

PRO LOSIGNE PROGRAMMENTAL SWEDERMENT AND STREET SAND AND STRE

EXISTING UTILITY INFORMATION SHOWN ON THESE PLANS IS FURNISHED BY THE UTILITY COMPANIES AND/OR THE SURVEYOR AND THE ACCURACY THEREOF IS NOT THE RESPONSIBILITY OF MARATHON ENGINEERING & ENVIRONMENTAL SERVICES, INC. IT IS THE RESPONSIBILITY OF THE OWNERS AND/OR CONTRACTOR TO CALL 1-800-272-1000 FOR FIELD LOCATION OF UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION.

DRAFT 1 INITIAL SUBMISSION
ISSUE DATE ISSUE NO. SUBMISSION/REVISION
BHT MULLICA TOWNSHIP

SHI 35, 8L 3501, LDIS 1 & 2, 8L 3505, LOT 1, 8L 3505

EXISTING UTILITY INFORMATION SHOWN ON THESE PLANS IS FURNISHED BY THE UTILITY COMPANIES AND/OR THE SURVEYOR AND THE ACCURACY THEREOF IS NOT THE RESPONSIBILITY OF MARATHON ENGINEERING & ENVIRONMENTAL SERVICES, INC. IT IS THE RESPONSIBILITY OF THE OWNERS AND/OR CONTRACTOR TO CALL 1-800-272-1000 FOR FIELD LOCATION OF UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION.

DRAFT 1 INITIAL SUBMISSION
ISSUE DATE ISSUE NO. SUBMISSION/REVISION

BHT MULLICA TOWNSHIP

SIT 35, R. 3903, LOTS 1 & 2, R. 3904, LOTS 1 & 2, R. 3905, LOT 1, R. 3905, LOT 1

TOWNSHIP OF MULLICA, ATLANTIC COUNTY, NEW JERSEY

MARATHON

Engineering & Environmental Services

Swedesboro Office


3 Killdeer Court, Suite 302, Swedesboro, NJ 08085
ph (866) 241-9705 fax (866) 241-9705 fax (866) 241-9705 fax (866) 241-9705


Certificate of Authorization #24GA27995700


DAVID J. FLEMING, P.E.


PRO LOSIGNE PROGRAMMENTAL SWINGERM, M. AR HAPPROVED AND SWINGERM MARKED AND SWINGERM MARKE

EXISTING UTILITY INFORMATION SHOWN ON THESE PLANS IS FURNISHED BY THE UTILITY COMPANIES AND/OR THE SURVEYOR AND THE ACCURACY THEREOF IS NOT THE RESPONSIBILITY OF MARATHON ENGINEERING & ENVIRONMENTAL SERVICES, INC. IT IS THE RESPONSIBILITY OF THE OWNERS AND/OR CONTRACTOR TO CALL 1-800-272-1000 FOR FIELD LOCATION OF UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION.









GENERAL NOTES

- ALL APPLICABLE EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE IN PLACE PRIOR TO ANY GRADING OPERATION AND/OR INSTALLATION OF PROPOSED STRUCTURES OR
- SOIL EROSION AND SEDIMENT CONTROL PRACTICES ON THIS PLAN SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW
- APPLICABLE EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE LEFT IN PLACE UNTIL CONSTRUCTION IS COMPLETED AND/OR THE AREA IS STABILIZED
- . THE CONTRACTOR SHALL PERFORM ALL WORK, FURNISH ALL MATERIALS AND INSTALL ALL MEASURES REQUIRED TO REASONABLY CONTROL SOIL EROSION RESULTING FROM CONSTRUCTION OPERATIONS AND PREVENT EXCESSIVE FLOW OF SEDIMENT FROM THE CONSTRUCTION SITE.
- ANY DISTURBED AREA THAT IS TO BE LEFT EXPOSED FOR MORE THAN THIRTY (30) DAYS AND NOT SUBJECT TO CONSTRUCTION TRAFFIC SHALL IMMEDIATELY RECEIVE A TEMPORARY SEEDING AND FERTILIZATION IN ACCORDANCE WITH THE NEW JERSEY STANDARDS AND THEIR RATES SHOULD BE INCLUDED IN THE NARRATIVE. IF THE SEASON PROHIBITS TEMPORARY SEEDING, THE DISTURBED AREAS WILL BE MULCHED WITH SALT HAY OR THE EQUIVALENT AND ANCHORED IN ACCORDANCE WITH THE NEW JERSEY STANDARDS (I.E. PEG AND TWINE, MULCH NETTING OR LIQUID MULCH BINDER).
- 6. IT SHALL BE THE RESPONSIBILITY OF THE DEVELOPER TO PROVIDE CONFIRMATION OF LIME FERTILIZER AND SEED APPLICATION AND RATES OF APPLICATION AT THE REQUEST OF THE CAPE-ATLANTIC CONSERVATION DISTRICT.
- ALL CRITICAL AREAS SUBJECT TO EROSION WILL RECEIVE A TEMPORARY SEEDING IN COMBINATION WITH STRAW MULCH AT A RATE OF 2 TONS PER ACRE, ACCORDING TO THE NEW JERSEY STANDARDS IMMEDIATELY FOLLOWING ROUGH GRADING.
- 8. THE SITE SHALL AT ALL TIMES BE GRADED AND MAINTAINED SUCH THAT ALL STORMWATER RUNOFF IS DIVERTED TO SOIL EROSION AND SEDIMENT CONTROL FACILITIES.
- 9. ALL SEDIMENTATION STRUCTURES WILL BE INSPECTED AND MAINTAINED ON A REGULAR BASIS AND AFTER EVERY STORM EVENT.
- 10. A CRUSHED STONE, TIRE CLEANING PAD WILL BE INSTALLED WHEREVER A CONSTRUCTION ACCESS EXISTS. THE STABILIZED PAD WILL BE INSTALLED ACCORDING TO THE STANDARD FOR STABILIZED CONSTRUCTION ACCESS.
- 11. PAVED ROADWAYS MUST BE KEPT CLEAN AT ALL TIMES.
- 12. ALL CATCH BASIN INLETS WILL BE PROTECTED ACCORDING TO THE CERTIFIED PLAN.
- 13. ALL DEWATERING OPERATIONS MUST DISCHARGE DIRECTLY INTO A SEDIMENT FILTER AREA. THE SEDIMENT FILTER SHOULD BE COMPOSED OF A SUITABLE FILTER FABRIC. (SEE DETAIL)
- 14. NJSA 4: 24-39, ET SEQ. REQUIRES THAT NO CERTIFICATE OF OCCUPANCY BE ISSUED BEFORE ALL PROVISIONS OF THE CERTIFIED SOIL EROSION AND SEDIMENT CONTROL PLAN HAVE BEEN COMPLIED WITH FOR PERMANENT MEASURES. ALL SITE WORK FOR THE PROJECT MUST BE COMPLETED PRIOR TO THE DISTRICT ISSUING A REPORT OF COMPLIANCE AS A PREREQUISITE TO THE ISSUANCE OF A CERTIFICATE OF OCCUPANCY BY THE MUNICIPALITY.
- 15. MULCHING IS REQUIRED ON ALL SEEDED AREAS TO ENSURE AGAINST EROSION BEFORE GRASS IS ESTABLISHED TO PROMOTE EARLIER VEGETATION COVER.
- 16. OFFSITE SEDIMENT DISTURBANCE MAY REQUIRE ADDITIONAL CONTROL MEASURES TO BE DETERMINED BY THE EROSION CONTROL INSPECTOR.
- 17. A COPY OF THE CERTIFIED SOIL EROSION AND SEDIMENT CONTROL PLAN MUST BE MAINTAINED ON THE PROJECT SITE DURING CONSTRUCTION.
- 18. THE CAPE ATLANTIC CONSERVATION DISTRICT SHALL BE NOTIFIED 48 HOURS PRIOR TO ANY LAND DISTURBANCE.
- 19. ANY CONVEYANCE OF THIS PROJECT PRIOR TO ITS COMPLETION WILL TRANSFER FULL RESPONSIBILITY FOR COMPLIANCE WITH THE CERTIFIED PLAN TO ANY SUBSEQUENT OWNERS.
- 20. IMMEDIATELY AFTER THE COMPLETION OF STRIPPING AND STOCKPILING OF TOPSOIL, THE STOCKPILE MUST BE STABILIZED ACCORDING TO THE STANDARD FOR TEMPORARY VEGETATIVE COVER. STABILIZE TOPSOIL PILE WITH STRAW MULCH FOR PROTECTION IF THE SEASON DOES NOT PERMIT THE APPLICATION AND ESTABLISHMENT OF TEMPORARY SEEDING. ALL SOIL STOCKPILES ARE NOT TO BE LOCATED WITHIN FIFTY (50) FEET OF A FLOODPLAIN,
- 21. ANY CHANGES TO THE SITE PLAN WILL REQUIRE THE SUBMISSION OF A REVISED SOIL EROSION AND SEDIMENT CONTROL PLAN TO THE CAPE ATLANTIC CONSERVATION DISTRICT. THE REVISED PLAN MUST BE IN ACCORDANCE WITH THE CURRENT NEW JERSEY STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL.

SLOPE, ROADWAY OR DRAINAGE FACILITY AND THE BASE MUST BE PROTECTED WITH A

- 22. METHODS FOR THE MANAGEMENT OF HIGH ACID PRODUCING SOILS SHALL BE IN ACCORDANCE WITH THE STANDARDS. HIGH ACID PRODUCING SOILS ARE THOSE FOUND TO CONTAIN IRON SULFIDES OR HAVE A pH OF 4 OR LESS.
- 23. TEMPORARY AND PERMANENT SEEDING MEASURES MUST BE APPLIED ACCORDING TO THE NEW JERSEY STANDARDS, AND MULCHED WITH SALT HAY OR EQUIVALENT AND ANCHORED IN ACCORDANCE WITH THE NEW JERSEY STANDARDS (I.E. PEG AND TWINE, MULCH NETTING OR LIQUID MULCH BINDER).
- 24. MAXIMUM SIDE SLOPES OF ALL EXPOSED SURFACES SHALL NOT BE CONSTRUCTED STEEPER THAN 3:1 UNLESS OTHERWISE APPROVED BY THE DISTRICT.
- 25. DUST IS TO BE CONTROLLED BY AN APPROVED METHOD ACCORDING TO THE NEW JERSEY STANDARDS AND MAY INCLUDE WATERING WITH A SOLUTION OF CALCIUM CHLORIDE AND
- 26. ADJOINING PROPERTIES SHALL BE PROTECTED FROM EXCAVATION AND FILLING OPERATIONS
- 27. USE STAGED CONSTRUCTION METHODS TO MINIMIZE EXPOSED SURFACES, WHERE APPLICABLE.
- 28. ALL VEGETATIVE MATERIAL SHALL BE SELECTED IN ACCORDANCE WITH AMERICAN STANDARDS FOR NURSERY STOCK OF THE AMERICAN ASSOCIATION OF THE NURSERYMEN AND IN ACCORDANCE WITH THE NEW JERSEY STANDARDS.
- 29. NATURAL VEGETATION AND SPECIES SHALL BE RETAINED WHERE SPECIFIED ON THE LANDSCAPE PLAN.
- 30. THE SOIL EROSION INSPECTOR MAY REQUIRE ADDITIONAL SOIL EROSION MEASURES TO BE INSTALLED, AS DIRECTED BY THE DISTRICT

CAPE ATLANTIC CONSERVATION DISTRICT 6260 OLD HARDING HIGHWAY MAYS LANDING, NJ 08330 (609) 625-3144 OR (609) 625-7000 EXT. 6154 FAX: (609) 625-7360

WORK HOURS AND NOISE CONTROL

1. CONSTRUCTION HOURS

SEDIMENT BARRIER.

- A. MONDAY THRU FRIDAY: 7:00AM-6:00PM (AS APPROVED BY ACIT)
- B. SATURDAY: 8:00AM-4:30PM (AS APPROVED BY ACIT)
- C. SUNDAY: NO WORK TO BE PERFORMED.
- D. THE HOURS STATED SHALL BE ADHERED TO UNLESS DUE TO WEATHER AND OR SCHEDULE CHANGES. ACIT SHALL BE NOTIFIED OF ALL TIME CHANGES.
- NOISE CONTROL EQUIPMENT TO BE UTILIZED SHALL BE STANDARD EARTH MOVING EQUIPMENT, CRANES, MIXERS, ETC. WHICH MEET STANDARDS ESTABLISHED BY STATE AND FEDERAL LAWS REGARDING THE AMOUNT OF NOISE PRODUCED.

DETAILED CONSTRUCTION SEQUENCE

- INSTALL TEMPORARY SOIL EROSION AND SEDIMENT CONTROL MEASURES.
- A. PLACE STABILIZED CONSTRUCTION ENTRANCE WHERE INDICATED ON PLAN. B. PLACE SILT FENCE AND INLET PROTECTION FOR PROPOSED INLETS WHERE INDICATED ON 1. CULTIVATED SOD IS PREFERRED OVER NATIVE SOD. SPECIFY "CERTIFIED SOD", OR OTHER
- 2. CLEAR AND GRUB CONSTRUCTION AREA AND DEMOLITION OF EXISTING IMPROVEMENTS.
- CONSTRUCT BASINS.
- 4. ROUGH GRADE SITE.
- INSTALL UNDERGROUND UTILITIES, DRAINAGE AND SUBSURFACE DRAINAGE BASINS. THE
- SUBSURFACE DRAINAGE SHALL BE PROTECTED FROM SILTS ENTERING. 6. CONSTRUCT BUILDING AND SITE FEATURES.
- CONSTRUCT PAVING.
- 8. TOPSOIL, LIME, FERTILIZE, SEED AND STABILIZE AS REQUIRED.

THE CAPE ATLANTIC SOIL CONSERVATION DISTRICT.

- REMOVE CONSTRUCTION SILTS FROM WITHIN BASINS AND REMOVE FROM SITE. REPLACEMENT
- SOILS TO BE INSTALLED IF REQUIRED AND PLACE SAND BOTTOM. 10. REMOVE SOIL CONSERVATION MEASURES UPON STABILIZATION OF SITE AS APPROVED BY

TEMPORARY VEGETATION

- TEMPORARY VEGETATIVE COVER: ESTABLISH TEMPORARY VEGETATIVE COVER ON SOILS EXPOSED FOR PERIODS OF TWO TO 6 MONTHS WHICH ARE NOT BEING GRADED. NOT UNDER ACTIVE CONSTRUCTION OR NOT SCHEDULED FOR PERMANENT SEEDING WITHIN 60
- PRIOR TO HALTING CONSTRUCTION FOR PERIODS LONGER THAN 30 DAYS AND DURING THE OFF SEASON, THE CONTRACTOR SHALL STABILIZE WITH TEMPORARY VEGETATIVE COVER ALL EXPOSED SOILS.
- TEMPORARY VEGETATIVE COVER SHALL BE ACCOMPLISHED BY THE FOLLOWING METHODS AND MATERIALS:
- A. SITE PREPARATION GRADE AS NEEDED AND FEASIBLE TO PERMIT THE USE OF CONVENTIONAL EQUIPMENT FOR SEEDBED PREPARATION, SEEDING, MULCH APPLICATION, AND MULCH ANCHORING. INSTALL NEEDED EROSION CONTROL PRACTICES OR FACILITIES SUCH AS DIVERSIONS, GRADE STABILIZATION STRUCTURES, CHANNEL STABILIZATION MEASURES, SEDIMENT BASINS, AND WATERWAYS. IMMEDIATELY PRIOR TO SEEDING, THE SURFACE SHOULD BE SCARIFIED 6" TO 12" WHERE THERE HAS BEEN SOIL COMPACTION. THIS PRACTICE IS PERMISSIBLE ONLY WHERE THERE IS NO DANGER TO UNDERGROUND UTILITIES (CABLES, IRRIGATION SYSTEMS, ETC.).
- B. SEEDBED PREPARATION APPLY LIMESTONE AND FERTILIZER ACCORDING TO SOIL TESTS SUCH AS THOSE OFFERED BY RUTGERS UNIVERSITY SOIL TESTING LABORATORY. SOIL SAMPLE MAILERS ARE AVAILABLE FROM THE LOCAL COOPERATIVE EXTENSION SERVICE OFFICE. IF SOIL TESTING IS NOT FEASIBLE ON SMALL OR VARIABLE SITES, OR WHERE TIMING IS CRITICAL. THE CONTRACTOR MAY APPLY PULVERIZED DOLOMITIC LIMESTONE AT THE RATE OF 90 POUNDS PER 1000 SQUARE FEET. APPLY 10-20-10 FERTILIZER OR EQUIVALENT AT THE RATE OF 11 POUNDS PER 1000 SQUARE FEET. THE LIME AND FERTILIZER SHALL THEN BE "WORKED" INTO THE SOIL TO A DEPTH OF 4" WITH A DISC, SPRINGTOOTH HARROW OR OTHER SUITABLE EQUIPMENT.
- C. SEEDING SEEDING SHALL CONSIST OF PERENNIAL RYEGRASS APPLIED AT THE RATE OF 1 POUND PER 1000 SQUARE FEET DURING COOL SEASON OR WEEPING LOVEGRASS AT 5 LBS. PER ACRE DURING WARM SEASON PLANTING.
- D. MULCHING THE CONTRACTOR SHALL MULCH ALL NEWLY SEEDED AREAS WITH UNROTTED SMALL GRAIN STRAW OR HAY FREE OF SEEDS AT THE RATE OF 70 TO 90 POUNDS PER 1,000 SQUARE FEET. IT SHALL BE ANCHORED THROUGH THE USE OF THE PEG AND TWINE METHOD. THE PEG AND TWINE METHOD OF MULCH ANCHORING SHALL CONSIST OF DRIVING 8-10 INCH WOODEN PEGS TO WITHIN 2-3 INCHES OF THE SOIL SURFACE EVERY 4 FEET IN ALL DIRECTIONS. STAKES MAY BE DRIVEN BEFORE OR AFTER APPLYING MULCH. SECURE MULCH TO SOIL SURFACE BY STRETCHING TWINE BETWEEN PEGS IN A CRISS-CROSS AND A SQUARE PATTERN. SECURE TWINE AROUND EACH PEG WITH TWO OR MORE ROUND TURNS.
- . SEEDING DATE SEEDING DATES FOR TEMPORARY VEGETATION SHALL OCCUR BETWEEN MARCH 1 AND MAY 15 OR BETWEEN AUGUST 15 AND OCTOBER 1. IF SEED IS NOT PLANTED WITHIN THESE DATES, THE CONTRACTOR SHALL STABILIZE WITH (MULCH: HAY OR EQUIVALENT) AT A RATE OF 2 TONS PER ACRE AND ANCHORED AS SPECIFIED ABOVE.

PERMANENT VEGETATION

- PERMANENT VEGETATION: IMMEDIATELY FOLLOWING THE COMPLETION OF CONSTRUCTION ACTIVITIES AT THE SITE, THE CONTRACTOR SHALL STABILIZE WITH PERMANENT VEGETATIVE COVER, ALL EXPOSED AND DISTURBED SOILS.
- PERMANENT VEGETATIVE COVER SHALL BE ACCOMPLISHED AS SPECIFIED BELOW:
- A. SITE PREPARATION GRADE AS NEEDED AND FEASIBLE TO PERMIT THE USE OF CONVENTIONAL EQUIPMENT FOR SEEDBED PREPARATION, SEEDING, MULCH APPLICATION, AND MULCH ANCHORING. INSTALL NEEDED EROSION CONTROL PRACTICES OR FACILITIES SUCH AS DIVERSIONS, GRADE STABILIZATION STRUCTURES, CHANNEL STABILIZATION MEASURES, SEDIMENT BASINS, AND WATERWAYS. IMMEDIATELY PRIOR TO SEEDING. THE SURFACE SHOULD BE SCARIFIED 6" TO 12" WHERE THERE HAS BEEN SOIL COMPACTION. THIS PRACTICE IS PERMISSIBLE ONLY WHERE THERE IS NO DANGER TO UNDERGROUND UTILITIES (CABLES, IRRIGATION SYSTEMS, ETC.).
- B. TOPSOILING THE CONTRACTOR SHALL PREPARE AREAS TO BE STABILIZED WITH PERMANENT VEGETATIVE COVER BY APPLYING TOPSOIL TO A UNIFORM DEPTH OF 6". TOPSOIL SHOULD BE FRIABLE, LOAMY, FREE OF DEBRIS, OBJECTIONABLE WEEDS AND STONES. AND CONTAIN NO TOXIC SUBSTANCE OR ADVERSE CHEMICAL OR PHYSICAL CONDITION THAT MAY BE HARMFUL TO PLANT GROWTH. SOLUBLE SALTS SHOULD NOT BE EXCESSIVE (CONDUCTIVITY LESS THAN 0.5 MILLIMHOS PER CENTIMETER. MORE THAN 0.5 MILLIMHOS MAY DESICATE SEEDLINGS AND ADVERSELY IMPACT GROWTH). TOPSOIL HAULED IN FROM OFFSITE SHOULD HAVE A MINIMUM ORGANIC MATTER CONTENT OF 2.75 PERCENT. ORGANIC MATTER CONTENT MAY BE RAISED BY ADDITIVES.
- C. SEEDBED PREPARATION APPLY LIMESTONE AND FERTILIZER ACCORDING TO SOIL TESTS SUCH AS THOSE OFFERED BY RUTGERS UNIVERSITY SOIL TESTING LABORATORY. SOIL SAMPLE MAILERS ARE AVAILABLE FROM THE LOCAL COOPERATIVE EXTENSION SERVICE OFFICE. IF SOIL TESTING IS NOT FEASIBLE ON SMALL OR VARIABLE SITES, OR WHERE TIMING IS CRITICAL, IMMEDIATELY FOLLOWING TOPSOILING, THE CONTRACTOR SHALL APPLY PULVERIZED DOLOMITIC LIMESTONE AT THE RATE OF 90 POUNDS PER 1,000 SQUARE FEET AND FERTILIZER (10-10-10) OR EQUIVALENT AT THE RATE OF 11 POUNDS PER 1000 SQUARE FEET. THE LIME AND FERTILIZER SHALL THEN BE "WORKED" INTO THE SOIL TO A DEPTH OF 4" WITH DISC, SPRINGTOOTH HARROW OR OTHER SUITABLE EQUIPMENT.
- D. SEEDING (#12) MIXTURE SEED . (SEE BELOW) IF SOD IS USED SEE SOD SPECS. CONVENTIONAL SEEDING IS PERFORMED BY APPLYING SEED UNIFORMLY BY HAND, CYCLONE (CENTRIFUGAL) SEEDER, DROP SEEDER, DRILL OR CULTIPACKER SEEDER, EXCEPT FOR DRILLED, HYDROSEEDED OR CULTIPACKED SEEDINGS, SEED SHALL BE INCORPORATED INTO THE SOIL WITHIN 24 HOURS OF SEEDBED PREPARATION TO A DEPTH OF 1/4 TO 1/2 INCH, BY RAKING OR DRAGGING. DEPTH OF SEED PLACEMENT MAY BE 1/4 INCH DEEPER ON COARSE-TEXTURED SOIL.
- HYDROSEEDING IS A BROADCAST SEEDING METHOD USUALLY INVOLVING A TRUCK, OR TRAILER-MOUNTED TANK, WITH AN AGITATION SYSTEM AND HYDRAULIC PUMP FOR MIXING SEED, WATER AND FERTILIZER AND SPRAYING THE MIX ONTO THE PREPARED SEEDBED. MULCH SHALL NOT BE INCLUDED IN THE TANK WITH SEED. SHORT-FIBERED MULCH MAY BE APPLIED WITH A HYDROSEEDER FOLLOWING SEEDING. HYDROSEEDING IS NOT A PREFERRED SEEDING METHOD BECAUSE SEED AND FERTILIZER ARE APPLIED TO THE SURFACE AND NOT INCORPORATED INTO THE SOIL. WHEN POOR SEED TO SOIL CONTACT OCCURS, THERE IS A REDUCED SEED GERMINATION AND GROWTH.
- E. MULCHING THE CONTRACTOR SHALL MULCH ALL NEWLY SEEDED AREAS WITH UNROTTED SMALL GRAIN STRAW OR HAY FREE OF SEEDS AT THE RATE OF 70 TO 90 POUNDS PER 1,000 SQUARE FEET. IT SHALL BE ANCHORED THROUGH THE USE OF THE PEG AND TWINE METHOD. THE PEG AND TWINE METHOD OF MULCH ANCHORING SHALL CONSIST OF 8"-10" WOODEN PEGS TO WITHIN 2"-3" OF THE SOIL SURFACE EVERY 4 FEET IN ALL DIRECTIONS. STAKES MAY BE DRIVEN BEFORE OR AFTER APPLYING MULCH. SECURE MULCH TO SOIL SURFACE BY STRETCHING TWINE BETWEEN PEGS IN A CRISS-CROSS SQUARE PATTERN. SECURE TWINE AROUND EACH PEG WITH TWO OR MORE TURNS.
- F. SEEDING DATES SEEDING DATES FOR PERMANENT VEGETATION SHALL OCCUR BETWEEN FEBRUARY 1 AND APRIL 30. MAY 1 TO AUGUST 14 OR BETWEEN AUGUST 15 AND OCTOBER 3. IF SEED IS NOT PLANTED WITHIN THESE DATES, THE CONTRACTOR SHALL STABILIZE WITH MULCH AS SPECIFIED ABOVE.

#12 MIXTURE (LAWN)	LBS/ACRE	LBS/1000 S.F.
33.4% JUSTICE TALL FESCUE	116.9	2.67
33.4% REBEL EXADE TALL FESCUE	116.9	2
33.2% PENN 1901 TALL FESCUE	116.2	2.66
IF HYDROSEEDING IS USED ALL SEEDING	RATES SHALL BE IN	ICREASED BY 25%.

SOD (if sod is used the following specification shall be used)

IF SODDING IS USED SEE SOD SPECIFICATIONS.

- HIGH QUALITY CULTIVATED SOD. SOD SHOULD BE FREE OF WEEDS AND UNDESIRABLE COARSE WEEDY GRASSES.
- 3. SOD SHOULD BE OF UNIFORM THICKNESS, APPROXIMATELY 5/8 INCH, PLUS OR MINUS 1/4 INCH, AT TIME OF CUTTING. (EXCLUDES TOP GROWTH).
- 4. SOD SHOULD BE VIGOROUS AND DENSE AND BE ABLE TO RETAIN ITS OWN SHAPE AND WEIGHT WHEN SUSPENDED VERTICALLY WITH A FIRM GRASP FROM THE UPPER 10 PERCENT OF THE STRIP. BROKEN PADS OR TORN OR UNEVEN ENDS WILL NOT BE ACCEPTED.
- 5. FOR DROUGHTY SITES, A SOD OF KENTUCKY 31 TALL FESCUE AND BLUEGRASS IS PREFERRED OVER A STRAIGHT BLUEGRASS SOD.
- 6. ONLY MOIST, FRESH, UNHEATED SOD SHOULD BE USED. SOD SHOULD BE HARVESTED, DELIVERED AND INSTALLED WITHIN A PERIOD OF 36 HOURS.

I. SITE PREPARATION:

II. SOIL PREPARATION:

- A. GRADE AS NEEDED AND FEASIBLE TO PERMIT THE USE OF CONVENTIONAL EQUIPMENT FOR SEEDBED PREPARATION, SEEDING, MULCH APPLICATION, AND MULCH ANCHORING. IMMEDIATELY PRIOR TO SEEDING, THE SURFACE SHOULD BE SCARIFIED 6" TO 12" WHERE THERE HAS BEEN SOIL COMPACTION. THIS PRACTICE IS PERMISSIBLE ONLY WHERE THERE IS NO DANGER TO UNDERGROUND UTILITIES (CABLES, IRRIGATION SYSTEMS, ETC.).
- B. INSTALL NEEDED EROSION CONTROL PRACTICES AND FACILITIES, SUCH AS INTERCEPTOR DITCHES, DIKES AND TERRACES, EROSION STOPS AND DESILTING BASINS.
- A. APPLY LIMESTONE AND FERTILIZER ACCORDING TO SOIL TESTS SUCH AS THOSE OFFERED BY RUTGERS UNIVERSITY SOIL TESTING LABORATORY. SOIL SAMPLE MAILERS ARE AVAILABLE FROM THE LOCAL COOPERATIVE EXTENSION SERVICE OFFICE. IF SOIL TESTING IS NOT FEASIBLE ON SMALL OR VARIABLE SITES, OR WHERE TIMING IS CRITICAL, FERTILIZER MAY BE APPLIED AT THE RATE OF 500 POUNDS PER ACRE OR 11 POUNDS PER 1,000 SQUARE FEET OF 10-20-10 OR EQUIVALENT. IN ADDITION, 300 POUNDS 38-0-0 PER ACRE OR EQUIVALENT OF SLOW RELEASE NITROGEN MAY BE USED IN LIEU OF TOPDRESSING. APPLY LIMESTONE (EQUIVALENT TO 50 PERCENT CALCIUM PLUS MAGNESIUM OXIDES) AS FOLLOWS:

TONS / ACRE SOIL TEXTURE CLAY, CLAY LOAM & HIGH ORGANIC SOIL SANDY LOAM, LOAM & SILT LOAM LOAMY SAND, SAND

- B. WORK LIME AND FERTILIZER INTO THE SOIL AS NEARLY AS PRACTICAL TO A DEPTH OF 4 INCHES WITH A DISC, SPRINGTOOTH HARROW OR OTHER SUITABLE EQUIPMENT. THE FINAL HARROWING OR DISCING OPERATION SHOULD BE ON THE GENERAL CONTOUR. CONTINUE TILLAGE UNTIL A REASONABLY UNIFORM, FIRM SEEDBED IS PREPARED.
- C. REMOVE FROM THE SURFACE ALL OBJECTS THAT WOULD PREVENT GOOD SOD TO SOIL CONTACT AND REMOVE ALL OTHER DEBRIS SUCH AS WIRE, CABLE, TREE ROOTS, PIECES
- D. INSPECT SITE JUST BEFORE SEEDING. IF TRAFFIC HAS LEFT THE SOIL COMPACTED, THE AREA MUST BE RETILLED AND FIRMED AS ABOVE.

OF CONCRETE, CLODS, LUMPS OR OTHER UNSUITABLE MATERIAL.

III. SOD PLACEMENT:

- A. SOD STRIPS SHOULD BE LAID ON THE CONTOUR, NEVER UP AND DOWN THE SLOPE, STARTING AT THE BOTTOM OF THE SLOPE AND WORKING UP. ON STEEP SLOPES, THE USE OF LADDERS WILL FACILITATE THE WORK AND PREVENT DAMAGE TO THE SOD. DURING PERIODS OF HIGH TEMPERATURE, LIGHTLY IRRIGATE THE SOIL IMMEDIATELY PRIOR TO LAYING THE SOD.
- B. PLACE SOD STRIPS WITH SNUG, EVEN JOINTS THAT ARE STAGGERED. OPEN SPACES INVITE EROSION.
- C. ROLL OR TAMP SOD IMMEDIATELY FOLLOWING PLACEMENT TO INSURE SOLID CONTACT OF ROOT MAT AND SOIL SURFACE. DO NOT OVERLAP SOD. ALL JOINTS SHOULD BE BUTTED TIGHTLY IN ORDER TO PREVENT VOIDS WHICH WOULD CAUSE DRYING OF THE
- D. ON SLOPES GREATER THAN 3:1, SECURE SOD TO SURFACE SOIL WITH WOOD PEGS, WIRE STAPLES, OR SPLIT SHINGLES (8" TO 10" LONG BY 3/4" WIDE).
- E. SURFACE WATER CANNOT ALWAYS BE DIVERTED FROM FLOWING OVER THE FACE OF THE SLOPE, BUT A CAPPING STRIP OF HEAVY JUTE OR PLASTIC NETTING, PROPERLY SECURED, ALONG THE CROWN OF THE SLOPE AND EDGES WILL PROVIDE EXTRA PROTECTION AGAINST LIFTING AND UNDERCUTTING OF SOD. THE SAME TECHNIQUE CAN BE USED TO ANCHOR SOD IN WATER- CARRYING CHANNELS AND OTHER CRITICAL AREAS. WIRE STAPLES MUST BE USED TO ANCHOR NETTING IN CHANNEL WORK.
- F. IMMEDIATELY FOLLOWING INSTALLATION, SOD SHOULD BE WATERED UNTIL MOISTURE PENETRATES THE SOIL LAYER BENEATH SOD TO A DEPTH OF 4 INCHES. MAINTAIN OPTIMUM MOISTURE FOR AT LEAST TWO WEEKS.

IV. TOPDRESSING:

IF SLOW RELEASE NITROGEN (300 POUNDS 38-0-0 PER ACRE OR EQUIVALENT) IS USED IN ADDITION TO SUGGESTED FERTILIZER, THEN A FOLLOW-UP OF TOPDRESSING IS NOT

A. A. FALL INSTALLATION OF SOD WILL REQUIRE AN APPLICATION OF FERTILIZER SUCH AS 10-20-10 OR EQUIVALENT AT 400 POUNDS PER ACRE OR 10 POUNDS PER 1000 SQUARE FEET BETWEEN SEPTEMBER 1 AND OCTOBER 15.

DUST CONTROL:

DUST CONTROL SHALL BE ACCOMPLISHED BY THE METHODS DESCRIBED BELOW.

MATERIAL	WATER DILUTION	TYPE OF NOZZLE	APPLY GALLONS/AC			
ANIONIC ASPHALT EMULSION	7:1 COARSE SPRAY		1200			
LATEX EMULSION	12,5:1	FINE SPRAY	235			
RESIN IN WATER	4:1	FINE SPRAY	300			
POLYACRYLAMIDE (PAM) — SPRAY ON POLYACRYLAMIDE (PAM) — DRY SPREAD	APPLY ACCORDING TO MANUFACTURER'S INSTRUCTIONS. MAY ALSO BE USED AS AN ADDITIVE TO SEDIMENT BASINS TO FLOCCULATE AND PRECIPITATE SUSPENDED COLLOIDS. SEE SEDIMENT BASIN STANDARD, P. 26-1					
ACIDULATED SOY BEAN SOAP STICK	NONE	COARSE SPRAY	1200			

TILLAGE: TO ROUGHEN SURFACE AND BRING CLODS TO THE SURFACE. THIS IS A TEMPORARY EMERGENCY MEASURE WHICH SHOULD BE USED BEFORE SOIL BLOWING STARTS. BEGIN PLOWING ON WINDWARD SIDE OF SITE. CHISEL-TYPE PLOWS PLACED ABOUT 12 INCHES APART, AND SPRING TOOTHED HARROWS ARE EXAMPLES OF EQUIPMENT WHICH MAY PRODUCE THE DESIRED

SPRINKLING: SITE IS SPRINKLED UNTIL THE SURFACE IS WET.

STONE: COVER SURFACE WITH CRUSHED STONE OR COARSE GRAVEL.

BARRIERS: SOLID BOARD FENCES, SNOW FENCES, BURLAP FENCES, CRATE WALLS, BALES OF HAY AND SIMILAR MATERIAL CAN BE USED TO CONTROL AIR CURRENTS AND SOIL BLOWING. CALCIUM CHLORIDE: SHALL BE IN THE FORM OF LOOSE, DRY GRANULES OR FLAKES FINE ENOUGH TO FEED THROUGH COMMONLY USED SPREADERS AT A RATE THAT WILL KEEP SURFACE MOIST BUT NOT CAUSE POLLUTION OR PLANT DAMAGE. IF USED ON STEEPER SLOPES, THEN USE OTHER PRACTICES TO PREVENT WASHING INTO STREAMS, OR ACCUMULATION AROUND

STANDARD FOR TOPSOILING

TOPSOILING ENTAILS THE DISTRIBUTION OF SUITABLE QUALITY SOIL ON AREAS TO BE VEGETATED. PURPOSE: TO IMPROVE THE SOIL MEDIUM FOR PLANT ESTABLISHMENT AND MAINTENANCE.

WATER QUALITY ENHANCEMENT: GROWTH AND ESTABLISHMENT OF A VIGOROUS VEGETATIVE COVER IS

TO IMPROVE THE SOIL MEDIUM FOR PLANT AND MAINTENANCE. TO IMPROVE THE SOIL MEDIUM FOR PLANT ESTABLISHMENT AND MAINTENANCE

FACILITATED BY TOPSOIL, PREVENTING SOIL LOSS BY WIND AND RAIN OFFSITE AND INTO STREAMS AND OTHER STORMWATER CONVEYANCES. WHERE APPLICABLE: TOPSOIL SHALL BE USED WHERE SOILS ARE TO BE DISTURBED AND WILL BE

METHODS AND MATERIALS: 1. MATERIALS

- A. TOPSOIL SHOULD BE FRIABLE (1), LOAMY (2), FREE OF DEBRIS, OBJECTIONABLE WEEDS AND STONES, AND CONTAIN NO TOXIC SUBSTANCE OR ADVERSE CHEMICAL OR PHYSICAL CONDITION THAT MAY BE HARMFUL TO PLANT GROWTH. SOLUBLE SALTS SHOULD NOT BE EXCESSIVE (CONDUCTIVITY LESS THAN 0.5 MILLIMHOS PER CENTIMETER. MORE THAN 0.5 MILLIMHOS MAY DESICATE SEEDLINGS AND
- ADVERSELY IMPACT GROWTH). TOPSOIL HALED IN FROM OFFSITE SHOULD HAVE A MINIMUM ORGANIC MATTER CONTENT OF 2.75 PERCENT. ORGANIC MATTER CONTENT MAY BE RAISED BY ADDITIVES. B. TOPSOIL SUBSTITUTE IS A SOIL MATERIAL WHICH MAY HAVE BEEN AMENDED WITH SAND, SILT, CLAY, ORGANIC MATTER, FERTILIZER OR LIME AND HAS THE APPEARANCE OF TOPSOIL. TOPSOIL SUBSTITUTES MAY BE UTILIZED ON SITES WITH INSUFFICIENT TOPSOIL OR FOR ESTABLISHING PERMANENT VEGETATION. ALL TOPSOIL SUBSTITUTE MATERIALS SHALL MEET THE REQUIREMENTS OF TOPSOIL NOTED ABOVE. SOIL TESTS SHALL BE PERFORMED TO DETERMINE THE COMPONENTS OF
- SAND, SILT, CLAY, ORGANIC MATTER, SOLUBLE SALTS AND PH LEVEL. STRIPPING AND STOCKPILING A. FIELD EXPLORATION SHOULD BE MADE TO DETERMINE WHETHER QUANTITY AND OR QUALITY OF
- SURFACE SOIL JUSTIFIES STRIPPING. B. STRIPPING SHOULD BE CONFINED TO THE IMMEDIATE CONSTRUCTION AREA
- C. WHERE FEASIBLE, LIME MAY BE APPLIED BEFORE STRIPPING AT A RATE DETERMINED BY SOIL TESTS TO BRING THE SOIL PH TO APPROXIMATELY 6.5. IN LIEU OF SOIL TESTS, SEE LIME RATE GUIDE IN SEEDBED PREPARATION FOR PERMANENT VEGETATIVE COVER FOR SOIL STABILIZATION, PG. 4-1. D. A 4-6 INCH STRIPPING DEPTH IS COMMON, BUT MAY VARY DEPENDING ON THE PARTICULAR SOIL
- CAUSE OFF-SITE ENVIRONMENTAL DAMAGE. F. STOCKPILES SHOULD BE VEGETATED IN ACCORDANCE WITH STANDARDS PREVIOUSLY DESCRIBED HEREIN; SEE STANDARDS FOR PERMANENT (PG. 4-1) OR TEMPORARY (PG. 7-1) VEGETATIVE COVER FOR SOIL STABILIZATION. WEEDS SHOULD NOT BE ALLOWED TO GROW ON STOCKPILES.

E. STOCKPILES OF TOPSOIL SHOULD BE SITUATED SO AS NOT TO OBSTRUCT NATURAL DRAINAGE OR

- SITE PREPARATION A. GRADE AT THE ONSET OF THE OPTIMAL SEEDING PERIOD SO AS TO MINIMIZE THE DURATION AND AREA OF EXPOSURE OF DISTURBED SOIL TO EROSION. IMMEDIATELY PROCEED TO ESTABLISH
- VEGETATIVE COVER IN ACCORDANCE WITH THE SPECIFIED SEED MIXTURE. TIME IS OF THE ESSENCE. B. GRADE AS NEEDED AND FEASIBLE TO PERMIT THE USE OF CONVENTIONAL EQUIPMENT FOR SEEDBED PREPARATION, SEEDING, MULCH APPLICATION AND ANCHORING, AND MAINTENANCE. SEE THE
- STANDARD FOR LAND GRADING, PG. 19-1. C. AS GUIDANCE FOR IDEAL CONDITIONS, SUBSOIL SHOULD BE TESTED FOR LIME REQUIREMENT. LIMESTONE, IF NEEDED, SHOULD BE APPLIED TO BRING SOIL TO A PH OF APPROXIMATELY 6.5 AND
- INCORPORATED INTO THE SOIL AS NEARLY AS PRACTICAL TO A DEPTH OF 4 INCHES. D. IMMEDIATELY PRIOR TO TOPSOILING. THE SURFACE SHOULD BE SCARIFIED 6"TO 12" WHERE THERE HAS BEEN SOIL COMPACTION. THIS WILL HELP INSURE A GOOD BOND BETWEEN THE TOPSOIL AND
- SUBSOIL. THIS PRACTICE IS PERMISSIBLE ONLY WHERE THERE IS NO DANGER TO UNDERGROUND UTILITIES (CABLES, IRRIGATION SYSTEMS, ETC.) E. EMPLOY NEEDED EROSION CONTROL PRACTICES SUCH AS DIVERSIONS, GRADE STABILIZATION STRUCTURES, CHANNEL STABILIZATION MEASURES, SEDIMENTATION BASINS, AND WATERWAYS. SEE
- STANDARDS 11 THROUGH 42. APPLYING TOPSOIL A. TOPSOIL SHOULD BE HANDLED ONLY WHEN IT IS DRY ENOUGH TO WORK WITHOUT DAMAGING SOIL
- STRUCTURE; I.E., LESS THAN FIELD CAPACITY (SEE GLOSSARY) B. A UNIFORM APPLICATION TO A DEPTH OF 5 INCHES (UNSETTLED) IS RECOMMENDED. SOILS WITH A PH OF 4.0 OR LESS CONTAINING IRON SULFIDE SHALL BE COVERED WITH A MINIMUM DEPTH OF 12

INCHES OF SOIL HAVING A PH OF 5.0 OR MORE, IN ACCORDANCE WITH A STANDARD FOR

MANAGEMENT OF HIGH ACID PRODUCING SOIL (PG. 1-1).

FOOTNOTES:

FRIABLE MEANS EASILY CRUMBLES IN THE FINGERS, AS DEFINED IN MOST SOILS TEXTS. (2) LOAMY MEANS TEXTURE GROUPS CONSISTING OF COARSE LOAMY SANDS, SANDY LOAM, FINE AND VERY FINE SANDY LOAM, SILT LOAM, CLAY LOAM, SANDY CLAY LOAM AND SILTY CLAY LOAM TEXTURES AND HAVING LESS THAN 35% COARSE FRAGMENTS (PARTICLES LESS THAN 2MM IN SIZE) AS DEFINED IN THE GLOSSARY OF SOIL SCIENCE TERMS, 1996, SOIL SCIENCE SOCIETY OF AMERICA.



SUBMISSION / REVISION



BHT MULLICA TOWNSHIP

T 35, BL 3503, LOTS 1 & 2, BL 3504, LOTS 1 & 2, BL 3505, LOT 1, BL 3506, LOT 1, BL 3507, LOTS 1 & 2, BL 3508, LOT 1, BL 3509, LOT

TOWNSHIP OF MULLICA, ATLANTIC COUNTY, NEW JERSEY

DRAFT | 1 | INITIAL SUBMISSION

ISSUE DATE | ISSUE NO. |

SERVICES, INC. ARE INSTRUMENTS AS SHOWN T DRAWN BY SHEET

Engineering & Environmental Services

Swedesboro Office


3 Killdeer Court, Suite 302, Swedesboro, NJ 08085 ph (856) 241-9705 fax (856) 241-9709

Certificate of Authorization #24GA27995700

SK 23 0F 24 C1301

SK DJF

| BY | APPR




- 1. PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED. NOTE: WHEN USING CELL-O-SEED DO NOT SEED PREPARED AREA. CELL-O-SEED MUST BE INSTALLED WITH PAPER SIDE DOWN.
- 2. BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET IN A 6" DEEP X 6" WIDE TRENCH WITH APPROXIMATELY 12" OF BLANKET EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR THE BLANKET WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" APART IN THE BOTTOM OF THE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING. APPLY SEED TO COMPACTED SOIL AND FOLD REMAINING 12" PORTION OF BLANKET BACK OVER SEED AND COMPACTED SOIL. SECURE BLANKET OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED APPROXIMATELY 12" APART ACROSS THE WIDTH OF THE BLANKET.
- 3. ROLL THE BLANKETS (A.) DOWN OR (B.) HORIZONTALLY ACROSS THE SLOPE. BLANKETS WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE. ALL BLANKETS MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES/STAKES IN APPROPRIATE LOCATIONS AS SHOWN IN THE STAPLE PATTERN GUIDE. WHEN USING OPTIONAL DOT SYSTEM, STAPLES/STAKES SHOULD BE PLACED THROUGH EACH OF THE COLORED DOTS CORRESPONDING TO THE APPROPRIATE STAPLE PATTERN.
- 4. THE EDGES OF PARALLEL BLANKETS MUST BE STAPLED WITH APPROXIMATELY 2"-5" OVERLAP DEPENDING ON BLANKET TYPE. TO ENSURE PROPER SEAM ALIGNMENT, PLACE THE EDGE OF THE OVERLAPPING BLANKET (BLANKET BEING INSTALLED ON TOP) EVEN WITH THE COLORED SEAM STITCH ON THE PREVIOUSLY INSTALLED BLANKET.
- 5. CONSECUTIVE BLANKETS SPLICED DOWN THE SLOPE MUST BE PLACED END OVER END (SHINGLE STYLE) WITH AN APPROXIMATE 3" OVERLAP. STAPLE THROUGH OVERLAPPED AREA, APPROXIMATELY 12" APART ACROSS ENTIRE BLANKET WIDTH.

1. IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6"

MAY BE NECESSARY TO PROPERLY SECURE THE BLANKETS. 2. DEWITT, EXCELSIOR, EROSION CONTROL BLANKET WITH BIODEGRADABLE BLANKET MATERIAL AND PHOTO DEGRADABLE NETTING OR APPROVED EQUAL.


SLOPE BLANKET INSTALLATION DETAIL





CONSTRUCTION SPECIFICATIONS

- 1. PIT DIMENSIONS ARE VARIABLE, WITH THE MINIMUM DIAMETER BEING 2 TIMES THE STANDPIPE DIAMETER.
- 2. THE STANDPIPE SHOULD BE CONSTRUCTED BY PERFORATING A 12" TO 24" DIAMETER CORRUGATED OR PVC PIPE. THEN WRAPPING WITH 1/2" HARDWARE CLOTH AND GEATEXTILE FABRIC. THE PERFORATIONS SHALL BE $1/2" \times 6"$ SLITS OR 1" DIAMETER HOLES.
- 3. A BASE FILTER MATERIAL CONSISTING OF CLEAN GRAVEL OR ASTM C 33 STONE SHOULD BE PLACED IN THE PIT TO A DEPTH OF 12". AFTER INSTALLING THE STANDPIPE, THE PIT SURROUNDING THE STANDPIPE SHOULD THEN BE BACKFILLED WITH THE SAME FILTER MATERIAL.
- 4. THE STANDPIPE SHOULD EXTEND 12" TO 18" ABOVE THE LIP OF THE PIT OR THE RISER CREST ELEVATION (BASIN DEWATERING ONLY) AND THE FILTER MATERIAL SHOULD EXTEND 3" MINIMUM ABOVE THE ANTICIPATED STANDING WATER ELEVATION.
- 5. ▼ WATER SURFACE ELEVATION.
- 6. SEDIMENT CONTROL BAGS MUST BE DISPOSED OF ACCORDING TO MANUFACTURER'S INSTRUCTIONS. BAGS MAY NOT BE REUSED.

TEMPORARY SUMP PIT DURING CONSTRUCTION INLET PROTECTION DETAIL







OR APPROVED EQUAL

- MIRAFI 600X FABRIC OR APPROVED EQUAL SECTION A-A

PREFORMED SCOUR HOLE TABLE								
ENDWALL	LA	W	С	D	D50	Е		
HDWL-1	9	6	24"	18"	4"	8		
HDWL-2	4.5'	3'	18"	9"	4"	8"		


NOTES

1. FIFTY PERCENT, BY WEIGHT, OF THE RIP-RAP MIXTURE SHALL BE SMALLER THAN MEDIAN STONE SIZE DESIGNATED AS D50. THE LARGEST STONE SIZE IN THE MIXTURE SHALL BE 1.5 TIMES THE D50 SIZE. A THREE FOOT WIDE BY THREE FOOT DEEP TOE THE SCOUR HOLE. 3. THE D50 SIZE SHOWN IS THE MINIMUM SIZE

PREFORMED SCOUR HOLE DETAIL


N.T.S.

CALCULATED.




WALL SHALL BE CONSTRUCTED AT THE END OF

SEDIMENT CONTROL BAG FOR DEWATERING DETAIL N.T.S.



BAG MUST BE DISPOSED OF ACCORDING TO MANUFACTURER'S INSTRUCTIONS. BAGS MAY NOT BE REUSED.






1. TOPSOIL STOCKPILE SHALL BE SURROUNDED BY SILT FENCE.


2. STOCKPILE SHALL RECEIVE TEMPORARY VEGETATIVE STABILIZATION IN ACCORDANCE WITH THE STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW JERSEY IMMEDIATELY AFTER COMPLETION OF STOCKPILE.

N.T.S.

3. STOCKPILES ARE NOT TO BE LOCATED WITHIN FIFTY FEET OF A FLOODPLAIN, SLOPES, ROADWAY, OR DRAINAGE FACILITY.



SILT FENCE DETAIL N.T.S.



DRAFT 1 INITIAL SUBMISSION

SOIL EROSION AND SEDIMENT CONTROL DETAIL SHEET BHT DESIGN GROUP 5555 ANGLERS AVENUE, SUITE 27 FORT LAUDERDALE, FL 33301



Engineering & Environmental Services Swedesboro Office 3 Killdeer Court, Suite 302, Swedesboro, NJ 08085 ph (856) 241-9705 fax (856) 241-9709 Certificate of Authorization #24GA27995700 ENVIRONMENTAL SERVICES, INC. ARE INSTRUMENTS
RVICE IN RESPECT TO THE PROJECT. THEY ARE NOT
DED OR REPRESENTED TO BE SUITABLE FOR REUSE

AS SHOWN DRAWN BY SHEET SK 24 OF 24

SK DJF

BY APPR.

EXISTING UTILITY INFORMATION SHOWN ON THESE PLANS IS FURNISHED BY THE UTILITY COMPANIES AND/OR THE SURVEYOR AND THE ACCURACY THEREOF IS NOT THE RESPONSIBILITY OF MARATHON ENGINEERING & ENVIRONMENTAL SERVICES, INC. IT IS THE RESPONSIBILITY OF THE OWNERS AND/OR CONTRACTOR TO CALL 1-800-272-1000 FOR FIELD LOCATION OF UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION.